

Haryana Government Gazette EXTRAORDINARY

Published by Authority

© Govt. of Haryana

No. 119-2019/Ext.] CHANDIGARH, WEDNESDAY, JULY 17, 2019 (ASADHA 26, 1941 SAKA)

हरियाणा सरकार

नगर तथा ग्राम आयोजना विभाग

अधिसूचना

दिनांक 17 जुलाई, 2019

संख्या सी.सी.पी. (एन.सी.आर.)/डी.डी.पी./आर.आर./2019/1432 .—पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) की धारा 5 की उप—धारा (4) द्वारा प्रदत्त शिक्तयों का प्रयोग करते हुए, हरियाणा के राज्यपाल, इसके द्वारा, अनुबन्ध ख में विनिर्दिष्ट नियंत्रित क्षेत्र को लागू की जाने वाली प्रस्तावित और अनुबन्ध क तथा ख में दिए गए निर्बन्धनों तथा शर्तों सहित रायपुर रानी के ईर्द—गिर्द नियन्त्रित क्षेत्र के लिए निम्नलिखित प्रारूप विकास योजना 2031 ईस्वी का प्रकाशन करवाने का प्रस्ताव करते हैं।

इसके द्वारा नोटिस दिया जाता है कि इस अधिसूचना के राजपत्र में प्रकाशन की तिथि से तीस दिन की अवधि की समाप्ति पर अथवा इसके पश्चात् सरकार, प्रारूप विकास योजना रायपुर रानी 2031 ईस्वी पर, ऐसे आक्षेपों अथवा सुझावों, यदि कोई हों, सिहत जो निदेशक, नगर तथा ग्राम आयोजना विभाग, हिरयाणा, मुख्य संयोजक योजनाकार (एन.सी. आर.) सी—3 हुड्डा काम्पलैक्स, प्रथम ब्लाक, तृतीय तल, सैक्टर 6, पंचकूला को सम्बोधित करते हुए किसी व्यक्ति से प्रारूप विकास योजना के संबंध में इस प्रकार विनिर्दिष्ट अवधि की समाप्ति से पूर्व प्राप्त किये जाएं, विचार करेगी।

ड्राईंग

- 1. वर्तमान भूमि उपयोग योजना, ड्राईंग संख्या डी.टी.पी.(पी) 1063 / 2008, दिनांक 05 फरवरी, 2008
- 2. प्रारूप विकास योजना, ड्राईंग संख्या डी.टी.पी.(पी) 1442 / 2018, दिनांक 15 जनवरी, 2018

अनुबंध 'क'

रायपुर रानी, जिला पंचकूला के नियंत्रित क्षेत्र की प्रारूप विकास योजना—2031 ईस्वी पर व्याख्यात्मक टिप्पण।

(i) परिचय:-

इस क्षेत्र में आगामी विकास अर्थात् चंडीगढ़ तथा पंचकूला में सूचना प्रोद्यौगिकी पार्क की स्थापना, पंजाब के निकटवर्ती क्षेत्रों (डेराबसी के साथ—साथ जीरकपुर) का विकास, चंडीगढ़ घरेलू हवाई अड्डे का अंतराष्ट्रीय हवाई अड्डे में अपग्रेडेशन, द्रुतगामी संयोजकता के लिए राष्ट्रीय राजमार्ग—344 को चौड़ा करने की परियोजना, के परिणाम स्वरूप रायपुर रानी और उसके चारों ओर के क्षेत्र का व्यापक सामाजिक—आर्थिक तथा भौतिक विकास करना अनुभव किया गया है। इसके अतिरिक्त, पंचकूला शहरी सम्पदा संतृप्ति को संतुलित तथा हरियाणा के अन्य भागों से बेहतर संयोजकता के कारण, इस क्षेत्र में क्षेत्र के बाहर से बड़े पैमाने पर आव्रजन का सामना करना पड़ रहा, जिसके परिणाम स्वरूप मौजुदा अवसंरचना तथा आवास और अन्य सम्बंधित कार्यालयों की मांग को पूरा करने के लिए बड़े पैमाने पर विकास का दबाव है। तदनुसार, अनियमित विकास पर नियंत्रण करने तथा अनिवार्य अवसंरचना मुहैया कराने के उद्देश्य से क्षेत्र का विकास योजनाबंद ढंग से करने की आवश्यकता महसूस की गई है।

इस गाँव से गुजरने वाली अनुसूचित सड़क—33 द्वारा नियंत्रित क्षेत्र को विभाजित किया गया है और सभी तरफ से कृषि खेतों द्वारा परिबंद किया गया है। गाँव रायपुर रानी इस क्षेत्र में अन्य ग्रामीण आवास के लिए एक ब्लॉक मुख्यालय के साथ साथ नोडल आवास के रूप में कार्य करता है और दक्षिण—पूर्व की ओर पंचकूला से 33 किलोमीटर, चंडीगढ़ से 43 किलोमीटर की दूरी पर स्थित है। उपरोक्त के अलावा, यह डेराबसी में से गुजरने वाले राष्ट्रीय राजमार्ग—152 से 20 किलोमीटर की दूरी पर स्थित है, जो कि पंजाब राज्य का निकटतम शहरी बंदोबस्त है। इस क्षेत्र से निकटतम रेलवे स्टेशन भी डेराबस्सी में अवस्थित है। राज्य की औद्योगिक तथा निवेश नीति—2011 के अनुसार, यह क्षेत्र मध्यवर्ती विकास खण्ड की श्रेणी में आता है। गाँव रायपुर रानी की आबादी उत्तर में 30° 34′ 57″ अक्षांश में तथा पूर्व में 77°′01′13′ रेखांश में अनुसूचित सड़क—33 के निकट स्थित है। इस नगर में औद्योगिक गितविधियाँ मूल रूप से कृषि—आधारित है, तथापि, इस क्षेत्र के योजनाबंद ढंग से विकास के बाद, कोट बेहला का विकास —हरियाणा में अलीपुर शहरी परिसर और रायपुर रानी तथा पंजाब के निकटवर्ती क्षेत्रों के मुक्त उद्यम जोन, के विकास के बाद यह क्षेत्र अपने कार्यात्मक स्वरूप में व्यापक परिवर्तन की अनुभूति के लिए अनुमानित है। रायपुर रानी की आगामी मांग को पूरा करने के उद्देश्य से 281.79 हैक्टेयर अतिरिक्त क्षेत्र को 25000 अतिरिक्त आबादी को समायोजित करने के लिए शहरी योग्य क्षेत्र के रूप में जोड़ा गया है।

शहरी बस्ती में प्राकृतिक ट्रेल्स, वन, पार्क, खेल केन्द्र, समग्र जीवन प्रक्रिया को सुरक्षित रखते हुए जीवन के लिए दक्ष तथा जारी रखने योग्य अवसंरचना तथा सौम्य पर्यावरण वाला होगा। शहर, निवासियों की कारोबारी तथा व्यक्तिगत आवश्यकताओं दोनों को पूरा करने के लिए उच्च किस्म की अवसंरचना मुहैया करेगा। सिंचाई विभाग, हरियाणा ने इस क्षेत्र को बाढ़ ग्रस्त क्षेत्र के रूप में रिर्पोट किया है, इसलिए शहरी क्षेत्र को बाढ़ से बचाने के उद्देश्य से डांगरी नदी के किनारे एक बांध प्रस्तावित किया गया है।

(ii) भू-आकृति विज्ञान

यह क्षेत्र उत्तर से दक्षिण तक सामान्य रूप से ढलान वाला है। इस क्षेत्र की भूमि उपजाऊ है तथा भूजल तालिका लगभग 150 फुट है।

(iii) अवसंरचना की उपलब्धता

(क) उपयोगिताएं:-

वर्तमान में रायपुर रानी में मौजुदा 66 किलोवाट बिजली की आपूर्ति उपकेंद्र से की जा रही है। जल आपूर्ति जन स्वास्थ्य विभाग द्वारा लगाए गए नलकूप से मुहैया करवाई जा रही है। इस समय, जल 55 लीटर प्रति व्यक्ति प्रति दिन की दर से दिया जा रहा है। इस समय, क्षेत्र में कोई भी सीवरेज प्रणाली विद्यमान नहीं है। वर्षा जल को बाहर निकालने के लिए गाँवों में सड़कों के किनारे खुले नालों का निर्माण किया जाता है।

(ख) सामाजिक अवसंरचना:-

शिक्षा सुविधाएं मुहैया कराने के लिए यहां 6 प्राथमिक विद्यालय, 3 मिडिल विद्यालय तथा 2 माध्यमिक विद्यालय हैं। क्षेत्र की स्वास्थ्य आवश्यकताओं को पूरा करने के लिए एक प्राथमिक स्वास्थ्य केंद्र उपलब्ध है।

(iv) नगर का आर्थिक आधार / कार्य स्थिति:--

गाँव रायपुर रानी और इस नियन्त्रित क्षेत्र में आने वाले अन्य ग्रामीण बस्तियों का आर्थिक आधार मुख्य रूप से कृषि है। यहाँ खेती की जाने वाली मुख्य फसलों में गेहूँ, चावल तथा मक्का हैं। रायपुर रानी में वर्तमान बस अड़डे के निकट स्थानीय बाजार निकटवर्ती ग्रामीण बस्ती की आवश्यकताओं को भी पूरा करता है। इसके अतिरिक्त, कुछ लघु उद्योग जैसे चावल शेलर, आटा—चक्की, कृषि यंत्र तथा फर्नीचर इत्यादि और कुछ मुर्गी—पालन फार्म इस क्षेत्र में विद्यमान हैं।

(v) जनसंख्या / जनसांख्यिकी:--

चूँिक गाँव रायपुर रानी की आबादी इसकी स्थानिक लाभ तथा आस—पड़ोस के क्षेत्रों से इसकी तीव्रता से संयोजकता के कारण बहुत तेजी से बढ़ रही है। रायपुर रानी गांव की आबादी 1961 से 2001 तक 30 प्रतिशत के औसत दशकीय वृद्धि से 3 गुणा बढ़ी है। इस क्षेत्र के पूर्व दशक वृद्धि तथा सम्भाव्य विकास को ध्यान में रखते हुए रायपुर रानी की आबादी दशक वर्ष 2021 तथा 2031 के लिए 95 प्रतिशत की वृद्धि दर से वर्ष 2031 में 34,000 तक बढ़ने की संभावना है।

(vi) वर्तमान परिवहन नेटवर्क:-

यह क्षेत्र इस में से गुजरने वाले अनुसूचित सड़क—33 के द्वारा राज्य के अन्य भागों से अच्छी तरह से जुड़ा हुआ है। इसके अलावा, राष्ट्रीय राजमार्ग संख्या 344 के माध्यम से संयोजकता तथा रेलवे लाईन पंजाब में डेराबस्सी में 16 किलोमीटर की दरी पर उपलब्ध है। इस प्रकार क्षेत्र राज्य के अन्य भागों से भली—भांति जुड़ा हुआ है।

(vii) नियंत्रित क्षेत्र की घोषणा की आवश्यकताएं:-

वर्ष 2006 में, नियंत्रित क्षेत्र रायपुर रानी को अव्यवस्थित तथा अनियंत्रित विकास से बचने तथा उचित माध्यम से शहरी विकास मुहैया कराने के उद्देश्य से अधिसूचित किया गया था। लगभग 1077.75 हैक्टेयर का क्षेत्र हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग, अधिसूचना संख्या सी०सी०पी०(एन०सी०आर)/पंचकूला/आर.आर/सी.ए/2006/3047, दिनांक 04 अक्तूबर, 2006 द्वारा नियंत्रित क्षेत्र के रूप में घोषित किया गया था, जो हरियाणा राजपत्र में दिनांक 04 अक्तूबर, 2006 में प्रकाशित किया गया था।

(viii) प्रस्तावः

नियंत्रित क्षेत्र की गांव की लगभग 9028 व्यक्तियों की आबादी को वर्तमान गांव बस्ती में 282 व्यक्ति प्रति हैक्टेयर के घनत्व से समायोजित किया जाएगा तथा 25000 व्यक्तियों की प्रवासी आबादी सिहत बाकी की आबादी को 250 व्यक्ति प्रति हैक्टेयर के घनत्व सिहत 95.96 हैक्टेयर के क्षेत्र पर प्रस्तावित किए जा रहे आवासीय क्षेत्र में समायोजित किया जाएगा। उपरोक्त प्रस्तावित प्रवासी आबादी ग्रामीण भीतरी प्रदेश तथा चंडीगढ—पंचकूला—मोहाली के ट्राईसिटी से अनुमानित है, जिसमें आम जनता की पहुंच से बाहर अपवाद स्वरूप उच्चतर दर पर आवसीय आवास हैं तथा चंडीगढ में प्रस्तावित अंतरराष्ट्रीय वायुपतन से केवल लगभग 30 किलोमीटर को दूरी पर स्थित होने के कारण यह अन्य क्षेत्रों से बाहरी आबादी के आगमन को आकर्षित करने में मूल भूमिका अदा करेगा। इसके अतिरिक्त, यह शहरी केंद्र ट्राईसिटी में प्रवासी आबादी के दबाव को बढ़ाने में हमेशा सहायता भी करेगा।

(ix) भूमि उपयोग प्रस्ताव:-

281.79 हैक्टेयर क्षेत्र 122 व्यक्ति प्रति हैक्टेयर को सकल नगर घनत्व तथा 250 व्यक्ति प्रति हैक्टेयर के कुल आवासीय घनत्व से शहरी योग्य क्षेत्र के रूप में प्रस्तावित किया गया है। नियंत्रित क्षेत्र के कुल 1077.75 हैक्टेयर में से प्रारूप विकास योजना के लिए भूमि उपयोग प्रस्ताव 281.79 हैक्टेयर के क्षेत्र को सम्मिलित करेगा। सरकार ने इन स्कीमों के अधीन विशेष आबादी घनत्व नियत करने के लिए अर्फोडेबल ग्रुप हाऊसिंग पॉलिसी, नई एकीकृत अनुज्ञापन पॉलिसी तथा दीन दयाल जन आवास योजना अधिसूचित की है। इसके अतिरिक्त, विभाग सेक्टर सघनता से अधिक रिहायशी सैक्टरों में 20 प्रतिशत वर्ग आवास घटक भी ले रहा है। इसलिए, नगर के इन क्षेत्रों की आबादी तथा घनत्व में वृद्धि होगी।

नियंत्रित क्षेत्र के भीतर प्रस्तावित भूमि उपयोग का विस्तृत ब्यौरा निम्नानुसार है:-

नियंत्रित क्षेत्र में प्रस्तावित क्षेत्र भूमि उपयोग कुल क्षेत्र की प्रतिशतता (प्रतिशत क्रम में क्षेत्र) संख्या (हैक्टेयर) आवासीय 95.96 34.05 1 वाणिज्यिक 2 13.77 4 89 औद्योगिक 10.67 3 30.07 परिवहन तथा संचार 4 61.65 21.88 5 सार्वजनिक उपयोगिताएं 13.64 4.84 सरकारी तथा अर्ध 6 15.72 5.58

तालिका

टिप्पण:—कुल प्रस्तावित शहरी योग्य क्षेत्र 281.79+32.074=313.864 हेक्टेयर, 109.72 पी.पी.एच. का नगर घनत्व भूमि उपयोगों का वर्णन

1. रिहायशी:-

7

सरकारी

स्थान **कुल**

हरित पट्टी तथा खुले

34,000 व्यक्तियों की आबादी को समायोजित करने के लिए 250 व्यक्ति प्रति हैक्टेयर के प्रस्तावित घनत्व सिंहत 95.96 हैक्टेयर के क्षेत्र पर आवासीय सेक्टर 1, 9 तथा 10 प्रस्तावित किये गये हैं। प्रत्येक आवासीय सेक्टर को ड्राइंग में निर्दिष्ट सैक्टर घनत्व में विकसित किया जायेगा तथा इसके अतिरिक्त, नई एकीकृत अनुज्ञापन पॉलिसी (एन.आई.एल. पी), अर्फोडेबल ग्रुप आवास पॉलिसी, दीन दयाल जन आवास योजना (डी.डी.जे.ए.वाई), 20 प्रतिशत ग्रुप हाऊसिंग कम्पोनेंट पालिसी में यथा विहित घनत्व भी आवासीय सैक्टर में लागू होगी।

50.98

281.79

18.09

100.00

उपरोक्त के अतिरिक्त विकास योजना में निम्नलिखित उपबंध भी किए गये हैं:-

- (क) अनुमानित आबादी की अपेक्षा को पूरा करने के लिए आवासीय सैक्टरों में अवसंरचना के लिए क्षेत्र उपलब्ध करवाया जाएगा।
- (ख) आवासीय कॉलोनी / सैक्टर में सड़कों की न्यूनतम चौड़ाई 12 मीटर से कम नहीं होगी या लागू नीतियों के अनुसार होगी।
- (ग) आवासीय कॉलोनी / सेक्टरों में पार्कों / खुले स्थानों के लिए न्यूनतम क्षेत्र ऐसी रीति में योजनाबद्व किया जायेगा कि यह 2.5 वर्गमीटर प्रति व्यक्ति के न्यूनतम मानदंडों को पूरा करेगा।

2. वाणिज्यिक:--

वाणिज्यिक कार्यकलाप न केवल इस क्षेत्र की वर्तमान तथा प्रक्षेपित आबादी का प्रबन्ध करेगा बल्कि आस—पास की आबादी के लिए भी प्रबंध करेगा। 13.77 हैक्टेयर के क्षेत्र पर सैक्टर—8 में, शहर केंद्र खुदरा व्यापार, थोक व्यापार, कार्यालयों तथा बैंकों इत्यादि तथा 7.08 हैक्टेयर के क्षेत्र पर वर्तमान अनाज मंडी के लिए प्रस्तावित किया गया है।

3. औद्योगिक:--

30.07 हैक्टेयर (लगभग) का क्षेत्र सैक्टर—5 के लिए प्रस्तावित किया गया है। इस औद्योगिक जोन में केवल गैर—प्रदूषणकारी उद्योग ही अनुज्ञात होंगे।

4. परिवहन तथा संचार:-

इस समय यह क्षेत्र अनुसूचित सड़क—33 के माघ्यम से लिंक सड़कों से जुड़ा हुआ है। शहरीकरण प्रस्तावों को 45 मीटर चौड़ी बाह्य सड़क से परिबद्ध किया गया है, जबिक सैक्टर विभाजन सड़के 30 मीटर की चौड़ाई सिहत प्रस्तावित की गई है। इसके अलावा, परिवहन तथा संचार क्षेत्र भी 7.40 हैक्टेयर क्षेत्र पर सैक्टर—6 में प्रस्तावित किया गया है। इस अंचल के अधीन कुल क्षेत्र लगभग 61.65 हैक्टेयर है।

प्रस्तावित सड़कों का वर्गीकरण निम्नानुसार है:-

क्रम संख्या	वर्गीकरण	भूमि आरक्षण
(i)	वी—1	बाहर की ओर 30 मीटर चौड़ी हरित पट्टी सहित 45 मीटर चौड़ी बाह्य सड़क
(ii)	वी—2	दोनो ओर पर 30 मीटर चौड़ी हरित पट्टी सहित वर्तमान एस.आर—33 सड़क
(iii)	वी—3	30 मीटर चौडी सैक्टर विभाजक सड़क
(iv)	वी—4	वर्तमान सड़क को 30 मीटर तक चौड़ा किया जाना है।

अन्य सड़कों की चौडाई तथा संरेखण सैक्टर योजना के अनुसार तथा कालोनी की अनुमोदित अभिन्यास योजना के अनुसार होगा।

5. सरकारी उपयोगिता:-

लगभग 13.64 हैक्टेयर क्षेत्र प्रस्तावित आबादी की आगामी आवश्यकता को पूरा करने के लिए सैक्टर–4 में सार्वजनिक उपयोगिता के लिए प्रस्तावित किया गया है।

6. सरकारी तथा अर्ध-सरकारी उपयोग:-

शैक्षणिक, सांस्कृतिक, धार्मिक, संस्थागत, चिकित्सा तथा स्वास्थ्य सुविधाएं मुहैया करवाने के लिए 15.72 हैक्टेयर का क्षेत्र सैक्टर—2 में प्रस्तावित किया गया है।

7. खुले स्थान:-

30 मीटर चौड़ी प्रतिबंधित हरित पट्टी वर्तमान अनुसूचित सड़क—33 के दोनों ओर पर प्रस्तावित की गई है।इस हरित पट्टी के अधीन लगभग 48.44 हैक्टेयर का क्षेत्र आता है। इसके अतिरिक्त, 30 मीटर चौड़ी हरित प्रतिरोधक भी परिधीय सड़क के बाह्य ओर प्रस्तावित किया गया है। सैक्टर—3 तथा 7 (भाग) में शहरी स्तर के खुले स्थल प्रस्तावित किये गये हैं।

8. कृषि अंचल:-

नियन्त्रित क्षेत्र के भीतर शहरीकरण प्रस्ताव पास—पड़ोस में बाकी का क्षेत्र अर्थात् 767.88 हैक्टेयर कृषि अंचल के रूप में रहेगा। तथापि, यह अंचल, इस क्षेत्र के भीतर अनिवार्य निर्माण कार्यकलापों जैसे वर्तमान गाँव से संसक्त आबादी देह के विस्तार को दूर नहीं करेगा, यदि यह सरकार द्वारा अनुमोदित या प्रायोजित परियोजना तथा कृषि भूमि के अनुरक्षण तथा सुधार के लिए आवश्यक अन्य आनुषंगी सुविधाओं के रूप में किया गया है।

अंचल विनियम:-

भूमि उपयोग सम्बन्धी प्रस्तावों को अंचल विनियम (अनुबन्ध ख) बनाते हुए वैध बनाया जा रहा है जो इस विकास योजना का हिस्सा होंगे। ये विनियम भूमि उपयोग में परिवर्तन और विकास के मानकों को शासित करेंगे। इनमें सम्बद्ध तथा सहायक उपयोगों का भी विस्तार पूर्वक वर्णन किया जाएगा जो विभिन्न मुख्य भूमि उपयोगों में अनुमत किए जाएंगे तथा नियतन करेंगे कि भूमि उपयोग के सभी परिवर्तन तथा विकास, विकास तथा उचित नियन्त्रण को निर्दिष्ट करने के लिए प्रत्येक क्षेत्र के लिए विस्तृत सेक्टर योजनाएं तैयार करना सुनिश्चित करने के लिए सेक्टर योजना में दर्शाए गए ब्यौरों के अनुसार होगा।

अनुबन्ध-ख

अंचल विनियम

ड्राईंग संख्या डीoटीoपीo(पी) 1442 / 2018, दिनांक 15 जनवरी, 2018 में दर्शाए अनुसार रायपुर रानी के इर्दगिर्द नियंत्रित क्षेत्रों में भूमि का उपयोग तथा विकास को शासित करना।

I सामान्य

- 1. रायपुर रानी के इर्दगिर्द नियंत्रित क्षेत्रों के लिए विकास योजना का भाग रूप बनने वाले इन अंचल विनियमों को नियंत्रित क्षेत्र रायपुर रानी के लिए प्रारूप विकास योजना के अंचल विनियम कहा जायेगा।
- 2. इन विनियमों की अपेक्षाएं, प्रारूप विकास योजना में शामिल समूचे क्षेत्र की सीमा तक होंगी तथा पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) और उसके अधीन बनाये गये नियमों की अपेक्षाओं के अतिरिक्त होंगी।

II परिभाषायें :

इन विनियमों में,-

- (क) "अनुमोदित" से अभिप्राय है, सक्षम प्राधिकारी द्वारा अनुमोदित;
- (ख) **"भवन संहिता"** से अभिप्राय है, हरियाणा भवन संहिता, 2017;
- (ग) **"भवन नियमों"** से अभिप्राय हैं, नियमों के भाग-VII में अन्तर्विष्ट नियम;
- (घ) **"ड्राईंग"** से अभिप्राय है, ड्राईंग संख्या डी० टी० पी० (पी) 1442/2018, दिनांक 15 जनवरी, 2018।
- (ड.) **"फर्श क्षेत्र अनुपात"** से अभिप्राय है, सभी मंजिलों के कुल आच्छादित क्षेत्र तथा सौ के गुणक को प्लाट क्षेत्र से विभाजित करते हुए प्राप्त किया गया भागफल, अर्थात् :--

फर्श क्षेत्र अनुपात =<u>कुल आच्छादित क्षेत्र</u> x 100 प्लाट क्षेत्र

फर्श क्षेत्र अनुपात की गणना के प्रयोजन के लिए, कैंटिलीवर अनुमत छत प्रोजेक्शनो; लिफ्ट कमरा, ममटी, छज्जा, तहखाना या कोई फर्श यदि पार्किंग, सेवाओं और भंडारण, केवल पार्किंग/पैदल यात्री प्लाजा के लिए उपयोग हेतु प्रस्तावित स्टिलट क्षेत्र, (खुला), खुली सीढ़ी (ममटी के बिना), पहुँच के साथ या के बिना, छत अग्नि सीढ़ी, अलंद पानी की टंकी, अनुमत आकार के खुला आंगन के लिये उपयोग किया गया हैं, फर्श क्षेत्र अनुपात में गिना नहीं जाएगाः

परंतु स्टिलट से अगली मंजिल तक शाफ्ट, शूटस, लिफ्ट वैल तथा सीढ़ी के अधीन क्षेत्र, भूमि तल से फर्श क्षेत्र अनुपात केवल एक बार गिना जाएगाः

परंतु यह और कि यदि वेंटिलेशन शाफ्ट क्षेत्र 3 वर्ग मीटर से अधिक है, तो यह फर्श क्षेत्र अनुपात में नहीं गिना जाएगा;

- (च) **'ईधन स्टेशन'** से अभिप्राय है, ईंधन भरने वाला स्टेशन जो ऑटोमोबाइल के लिए ईंधन की खुदरा आपूर्ति प्रदान करता है, जिसमें पेट्रोल पम्प, सीएनजी स्टेशन, जैव ईंधन, चार्जिंग स्टेशन, बैटरी उपलब्ध स्टेशन आदि शामिल हैं:
- (छ) "वर्ग आवास" से अभिप्राय है, रिहायशी प्रयोजन के लिए फ्लैटों के रूप में डिजाईन तथा विकसित किये गये भवन या वर्ग आवास का अनुषंगी कोई भवन;
- (ज) **''हल्के उद्योग'**' से अभिप्राय है, ऐसा उद्योग जिसके कारण हानिकारक या घृणाजनक शोर, धुआं, गैस, भॉप गन्ध, धूल, बिहःस्राव और कोई अन्य अत्यधिक डिग्री का प्रदूषण न हो और बिजली द्वारा चालित हों;
- (झ) "स्थानीय सेवा ज़्द्योग" से अभिप्राय है, ऐसा उद्योग जिसका विनिर्मित माल और उत्पादन प्रायः स्थानीय क्षेत्र के भीतर उपभोग किया जाता हो, उदाहरणार्थ बेकरियां, आईसक्रीम विनिर्माण, वातित जल, बिजली से चलने वाली आटे की चिक्कयां, लोंड्री, ड्राईक्लीनिंग और रंगाई, स्वचालित गाड़ियों, स्कूटर तथा साईकलों की मरम्मत तथा सर्विस, घरेलू बर्तनों की मरम्मत, जूते बनाना और उनकी मरम्मत, ईधन डिपो आदि बशर्ते कि उनमें किसी ठोस ईंधन का प्रयोग न किया जाता हो;
- (ञ) "मध्यम उद्योग" से अभिप्राय है, हल्का उद्योग तथा स्थानीय सेवा उद्योग के अलावा सभी उद्योग और जो घृणाजनक और खतरनाक गंध तथा दुर्गन्ध न फैलाते हों;
- (ट) "व्यापक उद्योग" से अभिप्राय है, ऐसा उद्योग जो सरकार की अनुमित से स्थापित किया जाये और जो व्यापक हो, जिसमें 100 से अधिक कामगार नियुक्त हों तथा जिसमें ईंधन चालित शक्ति का प्रयोग किया जाये बशर्ते कि इसमें किसी प्रकार के हानिकारक तत्व न हों;
- (ठ) "भारी उद्योग" से अभिप्राय है, सरकार की अनुमित से सार्वजनिक या अर्ध—सार्वजनिक या निजी क्षेत्र में स्थापित किया गया उद्योग (प्लान्ट, मशीनरी इत्यादि की लागत जैसे कि सरकार की उद्योग नीति में परिभाषित हो);

- (ड) "घृणाजनक या परिसंकटमय उद्योग" से अभिप्राय है सरकार की अनुमित से स्थापित किया गया उद्योग और जिसमें अत्यधिक पूंजी लगी हो। जिसमें अत्यधिक धुंआ, शोर, स्पन्दन, दुर्गन्ध, अप्रिय या हानिकारक बिहःस्राव, विस्फोटक, ज्वलनशील सामग्री इत्यादि और समुदाय के स्वास्थ्य और सुरक्षा के लिए अन्य खतरनाक तत्व शामिल हों:
- (ढ) **''वास्तविक तिथि''** से अभिप्राय है, नीचे घोषित किए गए विभिन्न नियंत्रित क्षेत्रों की अधिसूचना के प्रकाशन की तिथिः

क्रम संख्य	नियंत्रित क्षेत्र तथा अधिसूचना संख्या	वास्तविक तिथि		
1.	हरियाणा राजपत्र दिनांक ४ अक्तूबर, २००६ में प्रकाशित हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग, अधिसूचना संख्या, सी.सी.पी.(एन.सी. आर)/पीकेएल/आर.आर/सी.ए(बी)२००६/३०४७ दिनांक ४ अक्तूबर, २००६ द्वारा अधिसूचित नियंत्रित क्षेत्र।	४ अक्तूबर, २००६		

- (ण) नियंत्रित क्षेत्र में किसी भूमि अथवा भवन के संबंध में "अननुरूप उपयोग" से अभिप्राय है, ऐसी भूमि अथवा भवन जो विकास योजना में क्षेत्र के उस भाग के लिए विनिर्दिष्ट मुख्य भूमि उपयोग के विपरीत हो;
- (त) "सार्वजनिक उपयोगिता सेवा भवन" से अभिप्राय है, ऐसा भवन जो सार्वजनिक उपयोगिता सेवाओं को चलाने के लिए अपेक्षित हो, जैसे जल सप्लाई, जल निकास, बिजली, डाक तथा तार तथा परिवहन तथा दमकल केन्द्र सहित कोई नगरपालिका सेवा;
- (थ) "नियमों" से अभिप्राय है, पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन नियम, 1965,
- (द) "सैक्टर सघनता और कॉलोनी सघनता", से अभिप्राय है, उस सैक्टर क्षेत्र तथा कॉलोनी क्षेत्र, जैसी भी स्थिति हो, में प्रति व्यक्तियों की संख्या;
- (ध) "सैक्टर क्षेत्र, और कॉलोनी क्षेत्र" से अभिप्राय है, विकास योजना में ऐसे रूप में दर्शाये गये सैक्टर क्षेत्र या कॉलोनी क्षेत्र;

व्याख्या

- (1) इस परिभाषा में ''सैक्टर क्षेत्र'' या ''कालोनी क्षेत्र'' से अभिप्राय है, सैक्टर या कालोनी का क्षेत्र जो कालोनी / सैक्टर की अनुमोदित अभिन्यास योजना पर ड्राईंग में दर्शाया गया है जिसमें सैक्टर या कालोनी, जैसे भी स्थिति हो, में भवन विकास के लिए अनुपयुक्त क्षेत्र शामिल नहीं है;
- (2) मुख्य सड़कों तथा उनकी निकटवर्ती हरित पट्टी, यदि कोई हो, के अधीन आने वाले क्षेत्र का 50 प्रतिशत लाभ प्लाटिड़ / ग्रुप आवास कालोनी की दशा में प्लाटऐबल क्षेत्र / फर्श क्षेत्रफल अनुपात के लिए अनुज्ञात किया जायेगा;
- (3) औद्योगिक कालोनी / सैक्टर से भिन्न कालोनी या सैक्टर की विन्यास योजना में, सड़कों, खुले स्थानों, विद्यालयों, सार्वजनिक तथा सामुदायिक भवन तथा अन्य सामूहिक उपयोगों के लिए आरक्षित भूमि कालोनी / सैक्टर के अधीन भूमि के कुल क्षेत्र के 45 प्रतिशत से कम नहीं होगी।
- (4) सैक्टर सघनता या कालोनी सघनता की संगणना के प्रयोजनों के लिए यह माना जायेगा कि सैक्टर क्षेत्र या कालोनी क्षेत्र का 50 प्रतिशत आवासीय प्लाटों के लिए उपलब्ध होगा जिसमें ग्रुप आवास के अधीन क्षेत्र भी शामिल होगा तथा प्रत्येक भवन प्लाट औसतन प्रत्येक तीन निवास ईकाइयों में 4.5 व्यक्ति प्रति निवास ईकाई या 13.5 व्यक्ति भवन प्लाट या कालोनी / ग्रुप आवास समूह की अंचल योजना में यथा सम्मिलित होगा। यद्यपि, दुकान तथा आवासीय प्लाट के मामले में केवल एक निवास इकाई मानी जायेगी:
- (5) उपरोक्त दी गई किसी बात के होते हुए भी, विनिर्दिष्ट पॉलिसी जैसे नई एकीकृत अनुज्ञापन पॉलिसी के अधीन अनुमोदित परियोजनाएं; प्लॉटऐबल क्षेत्र की बजाय फर्श क्षेत्र अनुपात तथा सघनता पैरामीटर से शासित होंगी:
- (न) **"स्थल आच्छादन"** से अभिप्राय है, भवन के भूतल क्षेत्र और स्थल क्षेत्र द्वारा आच्छादित क्षेत्र के बीच प्रतिशतता में अभिव्यक्त अनुपात;
- (प) "अधिनियम", "कालोनी", "उप—िनवेशक", "विकास योजना", "सैक्टर" और "सैक्टर योजना" शब्दों का वही अर्थ होगा, जो उन्हे पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) में दिया गया है;
- (फ) "फार्म गृह" से अभिप्राय है, किसी फार्म के स्वामी द्वारा अपनी भूमि पर निम्नलिखित प्रयोजनार्थ निर्मित घर है—
 - (i) निवास यूनिट अर्थात् मुख्य उपयोग;

(ii) फार्म छायाबान अर्थात् गौण उपयोग।

टिप्पणी:--

- (1) फार्म गृह का निर्माण "कृषि अंचल में आबादी देह से बाहर फार्म गृहों की व्यवस्था" संबंधी खण्ड XIX के अधीन दिये गये निर्बन्धनों से शासित होगा:
- (2) "फार्म शैड" ''भवन नियंत्रण और स्थल विशिष्टियों'', के सम्बन्ध में खंड XIX में उल्लेखित निर्बन्धनों द्वारा शासित होंगे।
- (ब) "टांड या पुश्तवान" से अभिप्राय है, कमरे के अन्दर बनाए गए अनुलम्ब खम्भे को छोड़कर, किसी भी स्वरूप की शैल्फ जैसे बहिर्गत भाग, बशर्ते जिसका बर्हिगत भाग एक मीटर से अधिक चौडा न हो ।
- (भ) **"अटारी"** से अभिप्राय है, अधिकतम 1.5 मीटर की ऊँचाई सहित अविशष्ट स्थल पर दो मंजिलों के बीच का मध्यवर्ती स्थल तथा जो केवल भंडारण प्रयोजन हेतू निर्मित की गई है अथवा अपनाई गई है;
- (म) **"परछती तल"** से अभिप्राय है, निम्न मंजिल का 1/2 (आधा) तक के सीमित क्षेत्र सहित तथा न्यूनतम ऊँचाई 2.3 मीटर सहित दो मंजिलों के बीच कोई मध्यवर्ती तल और ऊपरी तल स्तर से 2.3 मीटर (स्पष्ट ऊँचाई) से कम नहीं होगा :
- (य) "कृषि उपयोग साधन" से अभिप्राय है, ऐसा विकास तथा गतिविधियां, जो कृषि संबंधी कार्यों को करने में सहायक रूप में अपेक्षित है, जैसे कि नलकूप, पम्प, चैम्बर, वायु चक्की, सिंचाई, नाले, पक्के प्लेटफार्म, बाड़ लगाना तथा चारदीवारी बनाना, जल नलके आदि:
- (य क) "ग्रामीण उद्योग स्कीम" से अभिप्राय है, ऐसी औद्योगिक इकाई जो उद्योग विभाग द्वारा ग्रामीण उद्योग स्कीम के रूप में पंजीकृत हो;
- (य ख) "लघु उद्योग" से अभिप्राय है, ऐसी औद्योगिक इकाई जो उद्योग विभाग द्वारा लघु उद्योग के रूप में पंजीकृत हो;
- (य ग) "कृषि आधारित उद्योग" से अभिप्राय है, ऐसी औद्योगिक इकाई, जो खाद्यान्न, फलों या कृषि अपशिष्ट का उपयोग कच्चे माल के रूप में करती है;
- (य घ) "सूचना प्रौद्योगिकी औद्योगिक इकाई" से अभिप्राय है, हरियाणा सरकार की सूचना प्रौद्योगिकी नीति, 2000 के अनुबन्ध में तथा इस अधिसूचना के परिशिष्ट—1 में शामिल उद्योगों की श्रेणियां तथा / अथवा जो हरियाणा सरकार द्वारा, समय—समय पर परिभाषित की जाये;
- (य ड.) "साईबर पार्क / सूचना प्रौद्योगिकी पार्क" से अभिप्राय है, वह क्षेत्र जो केवल साफ्टवेयर विकास सम्बन्धी क्रिया कलापों का पता लगाने तथा सूचना प्रोद्योगिकी को समर्थ बनाने वाली सेवाओं के लिए विकसित हों, इसमें किसी भी प्रकार के विनिर्माण (असैम्बलिंग क्रियाकलापों सहित) की अनुमति प्रदान नहीं की जाएगी।
- (य च) "साईबर सिटी" से अभिप्राय है, केन्द्रकीय सूचना / प्रौद्योगिकी परिकल्पना के लिए विकसित और कम्पनियों / सूचना प्रौद्योगिकी आधारित सेवाओं के मध्यम तथा बड़े साफटवेयर उत्पन्न किए जाने के लिए अति उच्चतम गुणवत्ता का मूलभूत ढांचा, उत्तम परिस्थितियां और उच्च गित संचार से आत्मिनर्भर परिपूर्ण शहर, जहां विनिर्माण ईकाईयों को अनुमत नहीं किया जाएगा;
- (य छ) "हरित पट्टी" से अभिप्राय है, विकास योजना में दर्शाए गए सैक्टर / परिधि सड़कों के साथ-साथ की भू पट्टी जो भविष्य में सड़क को चौड़ा करने के लिए उपयोग हो; तथा
- (य ज) किन्हीं अन्य अभिव्यक्तियों का वही अर्थ होगा, जो उन्हे पंजाब अनुसूचित सड़क तथा नियंत्रित क्षेत्र, अनियमित विकास निर्बन्धन अधिनियम, 1963 (1963 का पंजाब अधिनियम 41) में दिया गया है।

III. मुख्य भूमि उपयोग / अंचल

- 1. (i) रिहायशी अंचल
 - (ii) वाणिज्यिक अंचल
 - (iii) औद्योगिक अंचल
 - (iv) परिवहन तथा संचार अंचल
 - (v) जन उपयोगिता अंचल
 - (vi) सार्वजनिक तथा अर्धसार्वजनिक अंचल (संस्थागत अंचल)
 - (vii) खुले स्थान अंचल
 - (viii) कृषि अंचल
- 2. मुख्य भूमि उपयोगों का वर्गीकरण परिशिष्ट 'क' के अनुसार है।

IV. सेक्टरों में विभाजन

उपर्युक्त अंचल विनियमन—III में क्रम संख्या—(i) से (vii) पर वर्णित मुख्य भूमि उपयोग, जो भवन प्रयोजनार्थ भूमि उपयोग हैं, जिन्हें इन सैक्टरों की मुख्य सड़कों के आरक्षण हेतु दर्शाई गई हदबन्दी के अनुसार सैक्टरों में विभाजित किया गया है और प्रत्येक सेक्टर को ड्राईंग में दिखाये अनुसार एक निश्चित संख्या दी गई है।

पुख्य उपयोगों में भूमि उपयोग संबंधी ब्यौरे:—

मुख्य, सहायक तथा गौण उपयोग जो इन विनियमों तथा नियमों के अन्य अपेक्षाओं के अध्याधीन हैं, को मुख्य भूमि उपयोग अंचल में अनुमति दी जा सकती है, उनकी सूची परिशिष्ट ख पर दी गई है जो इन विनियमों के साथ जोड़े गये है।

VI. विकास के लिए अनुपयुक्त सेक्टर:-

विभिन्न सैक्टरों में भवन परियोजनार्थ, भूमि उपयोग के लिए आरक्षण होते हुए भी, निदेशक, नियंत्रित क्षेत्र के सघन तथा किफायती विकास के दृष्टिगत अपने भूमि उपयोग में किसी प्रकार के परिवर्तन के लिए अथवा उस पर किसी भवन के निर्माण के लिए ऐसे समय तक अनुमित नहीं देगा जब तक वह अपनी संतुष्टि सुनिश्चित नहीं कर लेता है कि इन सैक्टरों के लिए जल सप्लाई, जल मल निकास व्यवस्था तथा अन्य सुविधायें, उपलब्ध नहीं हो जाती हैं।

VII. केवल सरकारी उपक्रमों के माध्यम से विकसित किये जाने वाले सैक्टर:-

सरकार अपने द्वारा या उसके अभिकरणों द्वारा, विकास के लिए कोई सेक्टर अधिसूचित कर सकती हैं, ऐसे मामले में ऐसे सेक्टरों में भूमि उपयोग के परिवर्तन या अनुज्ञप्ति प्रदान करने के लिए आगे कोई भी अनुमति अनुमत नहीं की जाएगी ।

VIII. मुख्य सड़कों के लिए भूमि आरक्षण:-

(1) ड्राईग में चिहिनत की गई मुख्य सड़कों के लिए भूमि का आरक्षण निम्न प्रकार से किया जायेगाः

क्रम संख्या	वर्गीकरण	भूमि आरक्षण
(i)	वी—1	बाहर की ओर 30 मीटर चौड़ी हरित पट्टी सहित 45 मीटर चौड़ी परिधीय सड़क।
(ii)	वी—2	दोनों ओर 30 मीटर चौड़ी हरित पट्टी सहित वर्तमान एस.आर—33 सड़क।
(iii)	वी—3	30 मीटर चौडी सैक्टर विभाजक सड़क।
(iv)	वी—4	वर्तमान सड़क को 30 मीटर तक चौड़ी की जानी है।

- (2) अन्य सड़कों की चौड़ाई और सीधाई, सैक्टर प्लान के अनुसार अथवा कालोनियों की अनुमोदित अभिविन्यास योजना के अनुसार होगी।
- (3) व्यापारयोग्य फर्श क्षेत्र अनुपात का लाभ विनिर्दिष्ट पॉलिसी के अनुसार सैक्टर सड़क या हरित पट्टी तथा खुला क्षेत्र अंचलों के अधीन आने वाली भूमि के लिए प्रदान की गई अनुज्ञप्तियों के लिए अनुज्ञात किया जा सकता है।

IX. अनुरूप उपयोग अर्थात् विद्यमान या भूमि उपयोग में वैध परिवर्तन की अनुमति प्राप्त:-

- विकास योजना में औद्योगिक अंचल से भिन्न अंचलों में दर्शाए गए विद्यमान उद्योगों के संबंध में, निदेशक द्वारा निर्धारित की जाने वाली नियत अविध, किन्तु दस वर्ष से अधिक न हों, के लिए ऐसे औद्योगिक अननुरूप उपयोग जारी रखने की अनुमति दी जाएगी; बशर्ते कि सम्बद्ध भवन का स्वामीः
 - (क) निदेशक को स्थल के बाह्य विकास के लिए, उस द्वारा यथा निर्धारित अनुपातिक प्रभारों तथा जब भी निदेशक द्वारा इस निमित्त ऐसा करने के लिए कहा जाये, के भूगतान का वचन देता है;
 - (ख) अंतरिम अवधि के दौरान निदेशक की संतुष्टि के अनुसार बहिःस्राव के निष्कासन की सुनिश्चित व्यवस्था करेः तथा
 - (ग) अनुरूप उपयोग के क्षेत्र में विद्यमान परियोजना के विस्तार की अनुमति नहीं होगी ।
- उन पिरयोजनाओं के बारे में, जिन्हें भूमि उपयोग की मान्य स्वीकृति है, तथा जो विकास योजना में अनुरूप उपयोग अंचल से भिन्न अवस्थित हैं, ऐसे अनुरूप उपयोग जारी रखने के लिए अनुमत किए जाएंगे, बशर्ते कि सम्बद्ध भवन का स्वामी,—
 - (क) निदेशक को स्थल के बाह्य विकास के लिए उस द्वारा यथा निर्धारित अनुपातिक प्रभारों तथा निदेशक द्वारा इस निमित्त ऐसा करने के लिए कहा जाये, के भुगतान का वचन देता है;
 - (ख) अंतरिम अवधि के दौरान निदेशक की संतुष्टि के अनुसार बहि:स्राव के लिए संतोषजनक व्यवस्था करे।

X. अननुरूप उपयोग बन्द करना:-

- (1) यदि किसी भूमि का अननुरूप उपयोग दो वर्ष या इससे अधिक अविध के लिए लगातार बन्द रहा हो, तो उसे समाप्त हुआ समझा जायेगा और केवल अनुरूप अनुमत उपयोग के अनुसार ही भूमि के पुनःउपयोग या पुनःविकास की अनुमति दी जायेगी।
- (2) यदि अनुरूप उपयोग भवन, आग, बाढ़, विस्फोट, भूकम्प, लड़ाई, दंगा या किसी अन्य प्राकृतिक आपदा से इसके पुनरूत्पादन मूल्य के 50 प्रतिशत या इससे अधिक क्षतिग्रस्त हो जाता है, तो उसे केवल अनुमत उपयोग के लिए पुनःविकसित करने की अनुमित दी जायेगी।
- (3) खण्ड IX के अधीन शामिल परियोजनाओं के समाप्त होने के बाद, भूमि केवल अनुरूप उपयोग के लिए पुनः विकसित करने या उपयोग में लाने के लिए अनुमत की जायेगी।
- (4) खण्ड IX (1) के अधीन नियत अविध की समाप्ति के बाद भूमि केवल अनुरूप उपयोग के लिए पुनः विकसित या उपयोग में लाने के लिए अनुमत की जाएगी।

XI. सेक्टर योजना और आंचलिक योजना के अनुरूप विकासः

विनियम—IX में यथा उपबन्धित को छोड़कर, मुख्य भूमि उपयोग में किसी भी भूमि को भवन निर्माण प्रयोजनार्थ उपयोग तथा विकास के लिए तब तक अनुमत नहीं किया जाएगा जब तक प्रस्तावित उपयोग और विकास, सेक्टर योजना और आंचलिक योजना अथवा अनुमोदित कालोनी योजना, जिसमें भूमि अवस्थित है, में दिखाये गये ब्यौरे के अनुसार न हो।

XII. अनुमोदित अभिविन्यास या आंचलिक योजना का भाग बनने वाले विशिष्ट स्थलः

किसी प्लाट पर भवन निर्माण या पुनःनिर्माण की अनुमति तब तक नहीं दी जायेगी जब तक -

- (i) प्लाट अनुमोदित कालोनी का भाग न हो या प्लाट ऐसे क्षेत्र में न हो, जिसके लिए विनियम XVII में यथा उपबन्धित अनुसार छूट दी गई है; तथा
- (ii) निदेशक की संतुष्टि अनुसार प्लाट तक पहुंच के लिए सड़क की व्यवस्था न हो और सड़क न बनी हो।

XIII. विभिन्न प्रकार के भवनों के प्लाटों का न्यूनतम आकारः

(1) विभिन्न प्रकार के उपयोगों के लिए प्लाटों के न्यूनतम आकार निम्न अनुसार होंगे:—

कम संख्या	भूमि उपयोग	आकार
त्तख्या		
(i)	रिहायशी प्लाट	50 वर्ग मीटर
(ii)	सरकार द्वारा अनुमोदित आर्थिक सहायता प्राप्त औद्योगिक आवास या गन्दी बस्तियों में रहने वालों के लिए आवास स्कीम में रिहायशी प्लाट	35 वर्ग मीटर
(iii)	दुकान एवं रिहायशी प्लाट	100 वर्ग मीटर
(iv)	शापिंग बूथ जिनमें सामने बरामदा या पत्थर तथा ईंट पैदल मार्ग शामिल हो	20 वर्ग मीटर
(v)	स्थानीय सेवा उद्योग प्लाट	100 वर्ग मीटर
(vi)	हल्के उद्योग प्लाट	250 वर्ग मीटर
(vii)	मध्यम उद्योग प्लाट	8000 वर्ग मीटर

(2) रिहायशी और वाणिज्य विकास के लिये वर्ग आवास कालोनी, प्लाटिड रिहायशी कालोनी और वाणिज्य कालोनी के लिए क्षेत्र मानदण्ड समय—समय पर अधिसूचित नीतियों के अनुसार होंगें। तथापि, यदि वर्ग आवास स्कीम हिरयाणा शहरी विकास प्राधिकरण या किसी अन्य सरकारी एजेंसी द्वारा जारी की जाती है, तो वर्ग आवास स्थल का आकार योजना में यथा विनिर्दिष्ट होगा।

XIV. विभिन्न प्रकार के भवनों के अन्तर्गत आच्छादित क्षेत्र, ऊँचाई और आकार:-

विशिष्ट प्लॉट/ स्थल के लिए पर अनुमत आच्छादित क्षेत्र, फर्श क्षेत्र अनुपात तथा ऊँचाई पैरामीटरों, भवन संहिता/नियमों तथा/ या ऐसे प्लाट/स्थल के जोनिंग प्लान में यथा अधिकथित विहित पॉलिसी द्वारा शासित होगी।

XV. भवनों की अगली और पिछली ओर भवन पंक्ति:-

ये भवन संहिता / नियमों के अनुसार तथा / या ऐसे क्षेत्र के जोनिंग प्लान में यथा अधिकथित उपबन्धित होगी।

XVI. वास्तुकला संबंधी नियंत्रण:-

जहां कहीं भी वास्तुकला संबंधी नियंत्रण आवश्यक समझा जाता है, तो प्रत्येक भवन हरियाणा भवन संहिता, 2017 के खण्ड 6.4 के अधीन बनाये गए वास्तुकला संबंधी नियंत्रण के अनुरूप होगा।

XVII. कृषि अंचल में भूमि उपयोग में ढील:-

कृषि अंचल में आने वाली किसी भूमि के मामले में, सरकार इस विकास योजना के उपबन्धों में निम्नलिखित हेतु ढील दे सकती है,—

- (क) भूमि के आवासीय अथवा औद्योगिक कालोनी में उपयोग तथा विकास हेतु, बशर्तें उपनिवेशक द्वारा यह भूमि वास्तविक तिथि से पहले उक्त उपयोग तथा विकास के लिए क्रय की गई हो और उपनिवेशक नियमानुसार इस प्रयोजन के लिए अनुमित प्राप्त करता है।
- (ख) व्यक्तिगत स्थल के रूप में भूमि उपयोग हेतु (औद्योगिक कालोनी से भिन्न) परन्त्—
 - (i) वास्तविक तिथि से पूर्व भूमि क्रय की गई हो;
 - (ii) सरकार की संतुष्टि हो गई हो कि उद्योग की आवश्यकता इस प्रकार की है कि उपयुक्त अंचल में वैकल्पिक स्थल के नियतन की प्रतीक्षा नहीं की जा सकती;
 - (iii) भू-स्वामी, नियमों के यथा अपेक्षित अधीन भवन निर्माण के लिए अनुमति प्राप्त करता है; तथा
 - (iv) भू—स्वामी, निदेशक द्वारा निर्धारित अनुपातिक प्रभारों जब कभी इस निमित्त निदेशक द्वारा मांग की जाये, का भुगतान निदेशक को करने का वचन देता है और अंतरिम अवधि में बिहःस्राव के निकास की संतोषजनक व्यवस्था करता है।

व्याख्या:— इस विनियम में प्रयुक्त शब्द "क्रय" से अभिप्राय है, विभिन्न प्रयोजनों इत्यादि हेतु ऐसी अवधि, जो सरकार द्वारा विनिर्दिष्ट की जाए, के लिए पूर्ण स्वामित्व अधिकारों / पट्टा अधिकारों का अर्जन।

XVIII. सघनता:-

दोनों ओर से 20 प्रतिशत की विभिन्नता सिंहत प्रत्येक रिहायशी सैक्टर, ड्राईग में दर्शायी गई सैक्टर सघनता तथा इसके अतिरिक्त, नई एकीकृत अनुज्ञापन पॉलिसी, दीन दयाल जन आवास योजना पॉलिसी तथा अफोर्डऐबल ग्रुप हाऊसिंग पॉलिसी में यथा विहित सघनता में विकसित किया जाएगा। 20 प्रतिशत ग्रुप हाऊसिंग कम्पोनन्ट पॉलिसी रिहायशी सैक्टर में भी लागू होगी।

XIX. कृषि अंचल में आबादी देह के बाहर फार्म गृहों की व्यवस्था:-

केवल भू—स्वामी (स्वामियों) को वास्तविक उपयोग के लिए फार्म गृहों की अनुमित दी जाएगी बशर्ते कि किसी शहरी क्षेत्र में उसका अपना कोई आवास नहीं हो, चूंकि कृषि अंचल में फार्म गृहों को अनुमत करने के लिए वास्तविक उद्देश्य फार्म के छोटे भाग पर कृषकों की आवासीय आवश्यकताओं को पूरा करना है तािक वह उस फार्म पर निवास करने के दौरान अपने कृषि उत्पाद की देख—रेख कर सकें। इसिलए आबादी देह के बाहर कृषि अंचल में निम्नलिखित शर्तों पर फार्म गृह अनुमत किया जा सकता है, यदि भूमि का क्षेत्र 2 एकड़ या इससे अधिक है:

	फार्म हाउस का आकार	आवासीय इकाई का मुख्य भवन	मुख्य आवासीय इकाई का अनुषंगी भवन
(i) स्थल आच्छादन	न्यूनतम 2 एकड तक परन्तु विकास प्लैन अनुसार सड़क आरक्षण तथा प्रस्तावित सड़क की चौड़ाई के अधीन आने वाली भूमि/क्षेत्र भूमि उपयोग में परिवर्तन की अनुमित हेतु मान्य नहीं होगी। किन्तु कृषि अंचल मेंआने वाले आवेदित 2 एकड़ क्षेत्र मे से हरित पट्टी/ प्रतिबधित पट्टी के अधीन आने वाले क्षेत्र को छोडते हुए शेष क्षेत्र 1.5 एकड़ से कम नहीं होना चाहिए।		फार्म की भूमि का एक प्रतिशत (मजदूरों / नौकरों के क्वार्टरों के लिए 40 प्रतिशत से अधिक का उपयोग नहीं किया जायेगा)
	3 एकड़ तक	375 वर्ग गज के समकक्ष रिहायशी प्लाट के लिये यथा लागू।	-सम-
	4 एकड़ तक और अधिक	500 वर्ग गज के समकक्ष रिहायशी प्लाट के लिये यथा	-सम-

		लागू।	
(ii) ড	वाई तथा मंजिल	11 मीटर, तीन मंजिलें	4 मीटर एक मंजिल

(iii) दूरी: कृषि भूमि के सभी किनारों से कम से कम 10 मीटर दूर बशर्तें कि यदि फार्म हाऊस से संबद्ध भूमि सड़क के साथ लगती है तो गृह का निर्माण सड़क के किनारे से कम से कम निम्नलिखित दूरी पर किया जायेगा:—

कम संख्या	सडक	चौड़ाई
(ক)	जहां सड़क अनुसूचित सड़क का बाईपास है	100 मीटर
(ख)	जहां सड़क अनुसूचित सड़क है	30 मीटर या जैसा विकास योजना में दर्शाया गया है।
(ग)	कोई अन्य सड़क	10 मीटर

(iv) पहुँच सड़क:-

राजस्व रिकार्ड में परिभाषित कोई राजस्व रास्ता / सड़क।

(v) तहखानाः—तहखाना, भू—तल आच्छादन की अधिकतम सीमा तक अनुमत किया जाएगा और उपयोग हरियाणा भवन संहिता, 2017 के अनुसार अनुज्ञात हैं।

(vi) पुश्तवान, अटारी तथा परछती तल:-

पुश्तवान, अटारी और परछती तल की अनुमित भवन के भीतर उक्त निर्बन्धनों के साथ—साथ विकास योजना के अंचल विनियमों के खण्ड—II में दी गई परिभाषा में नियत निर्बन्धनों के अध्यधीन दी जायेगी।

(vii) सेवायें, जल आपूर्ति तथा जल-निकास:-

- (क) यदि फार्म गृह का निर्माण किया जाता है, तो फार्म में मानव उपयोग के लिए अच्छी पीने योग्य जल आपूर्ति उपलब्ध होनी चाहिए।
- (ख) डेरी फार्म के मामले में छायावानों की सफाई हेतु खुली स्वच्छ निकास नालियां अथवा ढकी हुई निकास नालियों की व्यवस्था की जाये, सभी भवनों के मामले में, वर्षा जल के निकास हेतु निकास नालियों की व्यवस्था की जानी है।
- (ग) नियमों के उपबन्धों के अनुसार मानव और पशुओं के अपिशष्ट निस्तारण के लिए मलाश्य की व्यवस्था की जाये।
- (घ) मलाश्य और खुले कुएं अथवा नलकूप के बीच दूरी नियमों में यथा उपबन्धित अनुसार होगी ;
- (viii) स्वामी को फार्म हाऊस की मुख्य आवासीय इकाई और उसके अनुषंगी भाग के इर्द—गिर्द चार दीवारी के निर्माण की अनुमित दी जायेगी तथा फार्म के शेष क्षेत्र के इर्द—गिर्द कंटीली तारों वाली बाड़ लगाने की अनुमित होगी।
- (ix) केन्द्रीय भूजल बोर्ड द्वारा यथा घोषित अत्यधिक शोषित अथवा सकंटमय क्षेत्र से भिन्न क्षेत्र में फार्म हाऊस की स्थापना हेतु भुमि उपयोग में परिवर्तन की अनुमति पर विचार किया जायेगा :

परन्तु सरकार कृषि अंचल के उचित उपयोगिता के लिए राज्य सरकार/राज्य अभिकरण द्वारा प्रायोजित किसी स्कीम के लिए फार्म के न्यूनतम आकार में संशोधन कर सकती है।

XX. सूचना प्रौद्योगिकी इकाईयों और साईबर पार्कों / साईबर शहरों के लिए उपबन्ध:-

I. अवस्थिति

- (क) सूचना प्रौद्योगिकी इकाईयां केवल औद्योगिक क्षेत्र / औद्योगिक अंचल में अवस्थित होंगी;
- (ख) साईबर पार्क / सूचना प्रौद्योगिकी पार्क एकीकृत विकास के रूप में सैक्टर सड़क के साथ लगते हुए या तो औद्योगिक क्षेत्र या औद्योगिक अंचल में अवस्थित होंगे। यद्यपि, ऐसे पार्कों में किन्हीं विनिर्माण इकाईयों को अनुज्ञात नहीं किया जाएगा।
- (ग) साईबर शहर :- ऐसी सुविधा की अवस्थिति सरकार द्वारा सुनिश्चित की जाएगी।

II. आकार

क्रम संख्या	प्रकार	आकार
1	सूचना प्रौद्योगिकी औद्योगिक इकाई	1 से 5 एकड़
2	साईबर पार्क / सूचना प्रौद्योगिकी पार्क	5 से 15 एकड़
3	साईबर सिटी	न्यूनतम ५० एकड़

III. विविध:-

I. पार्किंग:-

पार्किंग समय समय पर यथासंशोधित हरियाणा भवन संहिता, 2017 के उपबन्धों के अनुसार होगी।

II. अन्य क्रियाकलापः-

- (क) आनुषांगिक वाणिज्यिक क्रियाकलाप जैसे बैंक, रैस्टोरैन्ट, इंश्योरैंस कार्यालय इत्यादि, को साईबर पार्क / सूचना प्रौद्योगिकी पार्क के कुल क्षेत्र के 4 प्रतिशत निर्बन्धन के अधीन रहते हुए अनुमित दी जायेगी;
- (ख) साईबर शहर के क्षेत्र का केवल 5 प्रतिशत क्षेत्र वर्ग आवास के लिए अनुमत किया जायेगा तथा इस साईबर शहर का कुल क्षेत्र 4 प्रतिशत वाणिज्यिक / संस्थागत उपयोगों के लिए अनुमत किया जायेगा;
- (ग) साईबर शहर में रिहायशी प्लाटिड विकास की अनुमित नहीं दी जायेगी;
- (घ) किसी साईबर शहर परियोजना के लिए यदि कृषि अंचल में अनुज्ञात हो, तो उद्यमी जल—आपूर्ति तथा अन्य सुविधाओं जैसे मल जलनिस्तारण / निकास नालिया इत्यादि का प्रबन्ध करेगा।
- III. सरकार कोई अन्य शर्त अधिरोपित कर सकती है जैसा समय–समय पर आवश्यक समझे।

XXI. संचार टावरों की स्थापना:-

नियंत्रिंत क्षेत्र के भीतर संचार टावर स्थापित करने के लिए अनुमित, समय—समय पर यथा सशोंधित विभाग की पालिसी / अनुदेशों दिनांक 10 मार्च, 2015 के अनुसार प्रदान की जाऐगी।

XXII. भूकंम्पीय आपदा से सुरक्षा:-

भारतीय मानक आई. एस. 1893:2002 के भूकम्पीय क्षेत्र मानचित्र के अनुसार विकास योजना का क्षेत्र भूकम्पीय क्षेत्र जोन IV अंतर्गत आता है तथा इसे उच्च जोखिम क्षेत्र माना गया है। उपरोक्त को ध्यान में रखते हुए, सम्पूर्ण शहरी विकास घटना तीव्रता 'VIII' की सम्भाव्यता हेतु सुरक्षा की जांच की जाएगी तथा भवनों तथा अवसंरचना में अपेक्षित भूकम्पीय प्रतिरोध, जो आवश्यक पाया जाए, उन्नत किया जाएगा।

XXIII. नियंत्रित क्षेत्र में स्थित ईंटों के भट्टे:-

नियंत्रित क्षेत्रों में स्थित ईंट भट्टे सक्षम प्राधिकारी द्वारा समय-समय पर जारी सम्बंधित नीति / दिशा निर्देशों के द्वारा शासित होंगें।

XXIV. विकास योजना में ढील:-

सरकार, अत्यन्त कठिनाई की दशा में अथवा वास्तविक तिथि से पूर्व निर्मित किसी ढांचे को बचाने के दृष्टिगत ऐसे विकास प्रभारों के भुगतान पर और ऐसी अन्य शर्तों पर, जो वह लगाना उचित समझे, साम्य और न्याय के सिद्धान्तों पर विकास योजना के किसी भी उपबन्ध में ढील दे सकती है।

परिशिष्ट क भूमि उपयोगों का वर्गीकरण

मुख्य कोड	उपकोड	मुख्य वर्ग	उपवर्ग			
100		रिहायशी	पड़ोस–पद्धति पर रिहायशी सैक्टर			
200		वाणिज्यिक				
	210		परचून व्यवसाय			
	220		थोक व्यवसाय			
	230		भांडागार और भंडारण			
	240		कार्यालय और बैंक जिसमें सरकारी कार्यालय भी शामिल हैं।			
	250		रैस्तरां, होटल तथा अस्थाई बोर्डिंग हाऊस, जिनमें धर्मशाला, पर्यटक गृह आदि			
			जैसे रिहायशी आवास की व्यवस्था वाली सार्वजनिक सहायता संस्थायें भी			
			शामिल हैं			
	260		वाणिज्यिक आधार पर सिनेमा तथा लोगों के एकत्रित होने वाले अन्य स्थान			
	270		व्यवसायिक स्थापनायें			
300		औद्योगिक				
	310		सेवा उद्योग			
	320		हल्के उद्योग			
	330		व्यापक उद्योग			
400		परिवहन तथा				
		संचार				
	420		सड़कें, सड़क परिवहन डिपो और पार्किंग क्षेत्र,			

मुख्य कोड	उपकोड	मुख्य वर्ग	उपवर्ग
	450		टेलीग्राफ केन्द्र, दूरभाष केन्द्रइत्यादि
	460		प्रसारण केन्द्र
	470		दूरदर्शन केन्द्र
500		जन उपयोगितायें	
		उपयागिताय	
	510		जल आपूर्ति संस्थापन जिसमें शोधन संयंत्र भी शामिल हैं
	520		जल निकास और सफाई संस्थापनायें जिनमें निस्तारण कार्य भी शामिल हैं,
	530		विद्युत शक्ति संयंत्र उपस्टेशन इत्यादि
	540		गैस संस्थापन और गैस कार्य
	550		ठोस अपशिष्ट प्रबन्धन स्थल
600		सरकारी और अर्धसरकारी	
	610	311111111	सरकारी प्रशासन, केन्द्रीय सचिवालय, जिला कार्यालय, विधि न्यायालय, जेलें, पुलिस थाने, राज्यपाल तथा राष्ट्रपति निवास
	620		शिक्षा, सांस्कृतिक और धार्मिक संस्थायें
	630		चिकित्सा तथा स्वास्थ्य संस्थायें
	640		मुख्यतः गैर वाणिज्यिक किस्म के थियेटर, आपेरा हाऊस इत्यादि जैसी सांस्कृतिक संस्थायें
700		खुले स्थान	c
	710	3	खेलकूद मैदान, स्टेडियम, क्रीड़ा मैदान
	720		पार्क
	730		हरित पट्टी, बाग तथा अन्य मनोरंजन संबंधी उपयोग
	740		कब्रिस्तान, शमशान घाटइत्यादि
	750		प्यूल स्टेशन तथा बस पंक्ति शैल्टर
	760		जल निकाय/झीलें
800		कृषि भूमि	
	890		डेयरी फार्मिंग

परिशिष्ट ख मुख्य भूमि उपयोगों के अधीन दी गई अनुमत गतिविधियां, सरकार द्वारा स्वीकृत पालिसी/मापदंडों तथा सैक्टर/कालोनी में सक्षम प्राधिकारी द्वारा स्थल पर यथा अनुमत अनुसार अनुमत की जाएगी।

I. रिहायशी जोन

(i)	आवासीय
(ii)	सामाजिक, सामुदायिक, धार्मिक और आमोद प्रमोद गृह
(iii)	जन उपयोगिता भवन
(iv)	शैक्षणिक भवन और सभी प्रकार के विद्यालय और महाविद्यालय, जहाँ आवश्यक हों
(v)	स्वास्थ्य संस्थायें
(vi)	सिनेमा
(vii)	वाणिज्यिक और व्यवसायिक कार्यालय
(viii)	परचून की दुकानें, ढाबे और रैस्तरां
(ix)	स्थानीय सेवा उद्योग
(x)	ईंधन स्टेशन
(xi)	बस स्टाप, तांगा, टैक्सी, स्कूटर तथा आटो / रिक्शा स्टैंड
(xii)	नर्सरियां और हरित गृह
(xiii)	रिहायशी उपयोग में अनुषंगी कोई अन्य छोटी–छोटी जरूरतें
(xiv)	सितारा होटल

(xv) क्लब / सामुदायिक केन्द्र

(xvi) संचार टावर

(xvii) अतिथि / बोर्डिंग आवास

(xviii) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

II. वाणिज्यिक जोन

- (i) परचून व्यापार
- (ii) थोक व्यापार
- (iii) भांडागार और भंडारण
- (iv) वाणिज्यिक कार्यालय और बैंक
- (v) रैस्तरां तथा अस्थाई आवास गृह जिसमें धर्मशाला और पर्यटक गृह आदि जैसे रिहायशी स्थान प्रदान करने वाले सार्वजनिक सहायता संस्थाएं शामिल हैं
- (vi) सिनेमा, होटल, मोटल तथा वाणिज्यिक आधार पर चलने वाले और लोगों के इकट्ठा होने वाले अन्य स्थान जैसे थियेटर, क्लब, ड्रामा क्लब आदि
- (vii) व्यावसायिक स्थापनायें
- (viii) प्रथम तथा उच्चतर मंजिलों पर निवास
- (ix)
 स्थानीय सेवा उद्योग

 (x)
 जन उपयोगिता भवन
- (xi) ईंधन स्टेशन और सर्विस गैरेज
- (xii) माल चढ़ाने और उतारने वाले यार्ड
- (xiii) पार्किंग स्थल, बस स्टाप, टैक्सी, तांगा, आटो / रिक्शा स्टैंड
- (xiv) नगर पार्क (xv) संचार टावर
- (xvi) कोई अन्य उपयोग, जिसे निदेशक लोकहित में विनिश्चित करे।

III औद्योगिक अंचल

- (i) हल्के उद्योग
- (ii) मध्यम उद्योग
- (iii) घृणाजनक और परिसंकटमय उद्योग
- (iv) भारी उद्योग
- (v) सर्विस उद्योग
- (vi) भांडारण और भंडारण
- (vii) पार्किंग, माल चढाने और उतारने वाले क्षेत्र
- (viii) ट्रक स्टैंड / बस स्टाप, टैक्सी तांगा और आटो / रिक्शा स्टैंड
- (ix) सेक्टर के कुल क्षेत्र की अधिकतम तीन प्रतिशत की सीमा के अनुसार जन उपयोगिता, सामुदायिकभवन, परचून की दुकानें, बैंक, ढाबे, रैस्टोरैन्ट, दो / तीन / पांच सितारा होटल तथा बीमा कार्यालयनिम्नानुसार हैं:—

	वाना कावालवानम्नानुसार ६.–								
क्रम	सुविधा	क्षेत्र		सैक्टर में	वाणिज्यिक	अधिकतम	फर्श क्षेत्र	पहुँच सड़क	
संख्या	का नाम	न्यूनतम	अधिकतम	कुल सुविधाएं	घटक	भूतल	अनुपात		
				सुविधाए		आच्छादन			
1	ढाबा	500	1000	2	50	40 प्रतिशत	0.40	न्यूनतम 18	3
		वर्गमीटर	वर्गमीटर		वर्गमीटर			मीटर	
2	रैस्टोरैन्ट	1000	2000	2	10 प्रतिशत	30 प्रतिशत	1.50	न्यूनतम 18	}
		वर्गमीटर	वर्गमीटर					मीटर	
3.	दो / तीन	1.0 एकड	2.5 एकड	2	15 प्रतिशत	30 प्रतिशत	वाणिज्यिक	न्यूनतम २४	ļ
	सितारा						योजनानुसार	मीटर	
	होटल								
4.	पांच	2.5 एकड	4 एकड़	1	15 प्रतिशत	30 प्रतिशत	वाणिज्यिक	सैक्टर	
	सितारा						योजनानुसार	विभाजित	
	होटल							सडक	
								जिस पर	ŗ
								सर्विस	
								सडक का	ſ
								प्रावधान	
								हो।	

- (x) ईंधन स्टेशन तथा सर्विस गैरेज
- (xi) निदेशक द्वारा अनुमत लिक्वीड पैट्रोलियम गैस गोदाम
- (xii) साईबर पार्क / सूचना प्रौद्योगिकी पार्क / सूचना प्रौद्योगिकी औद्योगिक इकाइयां
- (xiii) स्वास्थ्य सुविधाएं जैसे अस्पताल, औषधालय, नर्सिंग होम तथा क्लीनिकः

क्रम	सुविधा का	क्षेत्र		सैक्टर	रिहायशी	अधिकतम	फर्श
संख्या	नाम	न्यूनतम	अधिकतम	में कुल	घटक	भूतल	क्षेत्र
				सुविधाएं		आच्छादन	अनुपात
1	अस्पताल	2.5 एकड	5 एकड़	1	15 प्रतिशत	३३ प्रतिशत	1.00
2	औषधालय	1.0 एकड	1.5 एकड	1	15 प्रतिशत	३३ प्रतिशत	1.00
3	नर्सिंग होम	250 वर्गमीटर	500वर्गमीटर	2	शून्य	60 प्रतिशत	1.00
4.	क्लीनिक	250 वर्गमीटर	500वर्गमीटर	2	शून्य	60 प्रतिशत	1.00

- (xiv) औद्योगिक कालोनी कम से कम 15 एकड़ में होगी। इस क्षेत्र का उपयोग अपर मुख्य सचिव, नगर तथा ग्राम आयोजना विभाग हरियाणा चण्डीगढ़ की यथा अद्यतन संशोधित पालिसी संख्या मिसलेनियस388 / पी.ए.(आरबी) / 2015 / 7 / 16 / 2006—2टीसीपी, दिनांक प्रथम अक्तूबर, .2015 के अनुसार होगा।
- (xv) संचार टावर
- (xvi) तैयार मिश्रण कंकीट संयत्र, वेट मिश्रण संयत्र, गर्म मिश्रण संयत्र इत्यादि
- (xvii) धर्म कांटा
- (xviii) सर्विस गैरज, बिक्री / प्रदर्शन केन्द्र सह-सर्विस गैरज का विवरण निम्न अनुसार है:-

क्रम	सुविधा	क्षेत्र ((एकड़ में)	वाणिज्यिकघटक	अधिकतम	तल क्षेत्र	पहुंच मार्ग	ऊँचाई
संख्या	का नाम	न्यूनतम	अधिकतम		भूतल आच्छादन	अनुपात		
1	सर्विस गैरज	0.5	1	शून्य	60प्रतिशत	1.25	न्यूनतम १८ मीटर या सेक्टर रोड के साथ प्रस्तावित सर्विस रोड	18 ਸੀਟਾ
2	बिक्री प्रदर्शन केन्द्र—सह— सर्विस गैरज	0.5	2	अनुज्ञेय फर्श क्षेत्र अनुपात का 10 प्रतिशत	60प्रतिशत	1.25	न्यूनतम 18 मीटर या सेक्टर रोड के साथ प्रस्तावित सर्विस रोड	18 मीटर

टिप्पण:-*वाणिज्यिक घटक पर फीस तथा प्रभार वाणिज्यिक दरों पर उद्गृहीत किए जाएंगे;

- * विद्यमान/पहले से भूमि उपयोग परिवर्तन अनुमित प्राप्त सर्विस गैराज को बिकी/प्रदर्शन केन्द्रकी अनुमित देने हेतु उपरोक्त मानदण्डों को पूरा करने के अध्यधीन विचारा जाएगा।
- (xix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

IV परिवहन तथा संचार अंचल

- (i) रेलवे यार्ड, रेलवे स्टेशन और साईडिंग
- (ii) परिवहन नगर, सडकें और परिवहन डिपो और पार्किंग क्षेत्र
- (iii) हवाई अडडा और हवाई स्टेशन
- (iv) दूरभाष केन्द्र
- (v) प्रसारण केन्द्र
- (vi) दरदर्शन केन्द्र
- (vii) अनुमोदित स्थलों और स्थानों पर कृषि, बागवानी और नर्सरिज
- (viii) ईंधन स्टेशन और सर्विस गैरेज
- (ix) पार्किंग स्थल, बस स्टाप-शैल्टर, टैक्सी, टांगा और ओटो / रिक्शा स्टैंड
- (x) रसद केन्द्रों / कंटेनर यार्डस, अंर्तदेशीय कंटेनर डिपो, कंटेनर फ्रेट स्टेशन
- (xi) धर्म कांटा

- (xii) संचार टावर
- (xiii) सैक्टर के कुल क्षेत्र की अधिकतम 20 प्रतिशत की सीमा तक भांडागार
- (xiv) वर्तमान नीति के अनुसार ढाबा।

V जनउपयोगितायें

- (i) जल सप्लाई, संस्थापनाएंजिसमें शोधन संयंत्र भी शामिल हैं
- (ii) जल निकास और सफाई स्थापनाएं इसमें मलजल शोधन संयंत्र तथा निपटान कार्य भी शामिल हैं
- (iii) विद्युत शक्ति संयंत्र तथा सबस्टेशन जिसमें ग्रिड सब स्टेशन भी शामिल हैं
- (iv) गैस संस्थापनाएं तथा गैस वर्कस
- (v) ठोस अपशिष्ट प्रबन्धन स्थल

VI सार्वजनिक तथा अर्धसार्वजनिक उपयोग अंचल

- (i) सरकारी कार्यालय, सरकारी प्रशासन केन्द्र, सचिवालय और पुलिस थाना
- (ii) शैक्षणिक, सांस्कृतिक और धार्मिक संस्थायें
- (iii) चिकित्सा स्वास्थ्य संस्थायें
- (iv) नागरिक / सांस्कृतिक और सामाजिक संस्थान जैसे थियेटर, ओपेरा हाउस इत्यादि जो मुख्यतः गैर वाणिज्यिक किस्म के हों।
- (v) रक्षा से सम्बन्धित भूमि
- (vi) ढाबा, रेस्टोरेन्ट निम्न अनुसार:-

क्रम	सुविधा का	क्षेत्र		सैक्टर में	वाणिज्यिक	अधिकतम	फर्श क्षेत्र अनुपात
संख्या	नाम	न्यूनतम	अधिकतम	कुल सविधाओं	घटक	भूतल आच्छादन	
				की संख्या			
1	ढाबा	500	1000	2	50	50 प्रतिशत	40 प्रतिशत
		वर्गमीटर	वर्गमीटर		वर्गमीटर		
2	रैस्टोरैन्ट	1000	2000	2	10	30 प्रतिशत	150 प्रतिशत
		वर्गमी0	वर्गमी0		प्रतिशत		

- (vii) संचार टावर
- (viii) ईंधन स्टेशन
- (ix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

VII खुले स्थान

- (i) खेलकूद मैदान, स्टेडियम तथा क्रीड़ा मैदान
- (ii) पार्क तथा हरित पट्टी, बाग तथा अन्य मनोरंजनात्मक उपयोग।
- (iii) कब्रिस्तान, शमशान घाटइत्यादि
- (iv) निदेशक की अनुमित से सड़कों के साथ फयूल फिलिंग स्टेशन, बस पंक्ति / शैल्टर
- (v) अनुसूचित सड़कों तथा मुख्य सड़कों के साथ हरित पट्टी में सार्वजनिक उपयोगिता सेवाएं जैसे इलैक्ट्रक ग्रिड स्टेशन, प्रेषण लाईनें, संचार लाईनें, जल आपूर्ति लाइनें सीवरेज लाईनें, ड्रैनेज लाईनें।
- (vi) जल निकाय/झील/जल पुर्नभरण क्षेत्र
- (vii) संचार टावर
- (viii) मेला स्थल तथा बह् उपयोगी मैदान
- (ix) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

VIII कृषि अंचल

- (i) कृषि, बागवानी, डेयरी और मुर्गी पालन
- (ii) आबादी देह के भीतर गांव घर
- (iii) अंचल विनियम XIX में यथा निर्धारित निर्बन्धनों के अध्यधीन, आबादी देह के बाहर फार्म हाऊस
- (iv) वन रोपण विकास तथा मनोरंजन के लिए उसका कोई भाग
- (v) आबादी देह के समीप वर्तमान गांव का विस्तार यदि यह परियोजना, केन्द्र सरकार या राज्य सरकार द्वारा अनुमोदित या प्रायोजित हो
- (vi) दुग्ध अवशीतन केन्द्र और पैस्चयूरीकरण केन्द्र
- (vii) बस अड्डा और रेलवे स्टेशन
- (viii) अनिवार्य भवनों सहित हवाई अड्डा
- (ix) बेतार केन्द्र
- (x) निदेशक द्वारा अनुमोदित स्थलों पर अनाज गोदाम, भंडारण स्थल

- मौसम कार्यालय (xi)
- भ-जल निकास और सिंचाई, पन बिजली कार्य और सिंचाई के लिए नलक्प (xii)
- टेलीफोन और बिजली प्रेषण लाईनें ओर खम्भे (xiii)
- खनन तथा उत्खनन कार्य जिसमें चूना तथा ईंटों के भट्टे, पत्थर, खदानें और क्रेशिंग शामिल है, जो (xiv) नियमों तथा अनुमोदित स्थल पर, के अधीन रहते हुए हैं।
- शमशान और कब्रिस्तान (xv)
- ईंधन स्टेशन और सर्विस गैरेज (xvi)
- नवीकरणीय और गैर नवीकरणीय उर्जा शक्ति संयंत्र (xvii)
- निदेशक के अनमोदन से तरल पैटोलियम पदार्थ भण्डारण गोदाम (xviii) ग्रामीण उदयोग रकीम / लघु उदयोग औदयोगिक इकाइयों को निम्नलिखित शर्तों की पूर्ति के अधीन रहते हुए अनुमति दी जाएगी, बशर्तें ऐसा स्थल रक्षा संस्थापनाओं, यदि कोई हो, के इर्द गिर्द रक्षा संकर्म (xix) अधिनियम, 1903 (1903 का केन्द्रीय अधिनियम 7) के अधीन वर्जित पट्टी के भीतर नहीं होना चाहिए।

क. स्थल मानदंड				
अंचल	मानदंड			
कम संभावित क्षेत्र	शहरीकरण क्षेत्र से 2 किमी के भीतर	शहरीकरण क्षेत्र से 2 किमी से अधिक		
	(परिधीय सड़कों को छोड़कर, यदि	(परिधीय सड़कों को छोड़कर, यदि		
	शहरी सीमा पर प्रस्तावित किया गया	शहरी सीमा पर प्रस्तावित किया गया		
	हो)	हो)		
	किसी भी क्षेत्र की गैर—प्रदूषणकारी	किसी भी क्षेत्र की ग्रीन और नारंगी		
	हरी श्रेणी इकाइयां	श्रेणी इकाइयां		
ख. पहुँच मानदंड				
मध्यम और औद्योगिक उपयोग के लिए कृषि क्षेत्र में भूमि उपयोग परिवर्तन अनुमति देने के लिए				
निम्न संभावित न्यन	नतम २० फीट चौदा राजस्व सदक / स	र्विजनिक सदक पर विचार किया जाएगा		

क्षेत्र

न्यूनतम 30 फीट चौड़ा राजस्व सड़क / सार्वजनिक सड़क पर विचार किया जाएगा । तथापि, यदि भूमि उपयोग की औदयोगिक परिवर्तन 5 करम (27.5 फूट) चौडा राजस्व मार्ग / सार्वजनिक सड़क पर दी गई है, तो उस सड़क पर भूमि उपयोग परिवर्तन अनुमति के लिए आवेदन, इस शर्त के अध्यधीन विचारा जाएगा कि आवेदन करने वाले साइट के सामने 6 कर्म (33 फुट) परियोजना प्रत्यार्तक दर्शाता है कि 1 करम (5.5 फ़्ट) चौड़ी पट्टी ग्राम पंचायत / स्थानीय प्राधिकरण को हिबबानैमा / उपहार के माध्यम से विस्तृत पट्टी के रूप में बनाने के लिए लागू की गई भूमि ।

अनुसूचित सड़कों, राष्ट्रीय राजमार्ग और राज्य राजमार्ग के अलावा सार्वजनिक संडक / रास्ता जिसकी (xx)चौड़ाई 30 फीट से कम है, पर गैर प्रदूषणकारी मध्यम और बड़े पैमाने पर कृषि आधारित उद्योग; बशर्ते कि ऐसी स्थापना, यदि कोई हो, के लिए यथा लागू सुरक्षा स्थापना के आसपास निर्वन्धित पट्टी के भीतर नहीं होना चाहिए ।

निर्बन्धित / हरित पट्टी के बाहर क्षेत्र में राष्ट्रीय राजमार्ग / अनुसूचित सड़कों के साथ ढाबे, बैंक्विट हाल, (xxi) लघ रैस्टोरेन्ट, मोटल, होटल रिर्सोटज तथा मन बहलाव पार्क / थीम पार्क निम्न अनसार होंगे:

कम	अनुज्ञेय गतिविधि	8	র	वाणिज्यक	अधिकतम	फर्श क्षेत्र
संख्या		न्यूनतम	अधिकतम	घटक	भूतल	अनुपात
					आच्छादन	
1	ढाबा	1000 वर्ग	1.0 एकड़	50 वर्ग	40 प्रतिशत	40
		मीटर		मीटर		प्रतिशत
2	रैस्टोरैन्ट	2000 वर्ग	1.0 एकड़	15 प्रतिशत	30 प्रतिशत	150
		मीटर				प्रतिशत
3	बैंकट सुविधाओं	2.5 एकड़	5 एकड़	15 प्रतिशत	30 प्रतिशत	150
	सहित मोटल					प्रतिशत
4	रिर्सोट	4.0 एकड़	10 एकड़	15 प्रतिशत	३० प्रतिशत	150
						प्रतिशत
5	मन–बहलाव	2.5 एकड़	10 एकड़	15 प्रतिशत	30 प्रतिशत	50
	पार्क / थीम पार्क					प्रतिशत

परन्तु पहुंच अनुज्ञा, यदि स्थल राष्ट्रीय राजमार्ग पर अवस्थित है तो भारतीय राष्ट्रीय राजमार्ग प्राधिकरण तथा यदि स्थल अनुसूचित सड़क पर अवस्थित है तो कार्यकारी अभियन्ता, लोक निर्माण विभाग (भवन तथा सडकें) से प्राप्त की गई है।

(xxii) बेंक्विट हालः

1110 6111	
अनुज्ञेय अचंल	कृषि अचंल
पहुंच	1. पहुंच सड़क की न्यूनतम चौडाई 18 मीटर होनी चाहिए।
	2. यदि स्थल अनुसूचित सड़क पर स्थित हो तो पहुंच अनुज्ञा कार्यकारी अभियता,
	लोक निर्माण विभाग (भवन तथा सड़कें) से अपेक्षित है।
	3. राष्ट्रीय राजमार्ग से भी पहुंच विचारी जा सकती है, यदि स्थल चौराहा / पहुंच
	मार्ग से न्यूनतम दूरी मानक पूरा करता हो तथा न्यूनतम 7 मीटर चौडी सेवा
	सड़क पर अवस्थित हो या आवेदक भारतीय राष्ट्रीय राजमार्ग प्राधिकरण से
	पहुंच की पूर्व अनुज्ञा प्रस्तुत करता है।
अपेक्षित क्षेत्र	न्यूनतम २.५ एकड्
	अधिकतम 5.00 एकड़
फर्श क्षेत्र	50 प्रतिशत
अनुपात	
भूतल	30 प्रतिशत
आच्छादन	
परिवर्तन प्राभार	वाणिज्यिक उपयोग के लिए विहित दर का 50 प्रतिशत
फर्श क्षेत्र	उपहार दुकान, एस टी डी बूथ, खिलौना केन्द्र तथा फूलों की दूकानें इत्यादि के लिए
अनुपात के	अनुमत फर्श क्षेत्र अनुपात को 10 प्रतिशत
भीतर अनुज्ञेय	
अनुषांगिक	
उपयोग	
पार्किंग	स्थल क्षेत्र का न्यूनतम 25 प्रतिशत
·	

टिप्पण:-

नगरपालिका सीमा के भीतर विवाह महल / बाँक्विट हॉल की व्यवस्था शहरी स्थानीय निकायों के विभाग द्वारा अनुमोदित तथा समय समय पर संशोधित नीति के अनुसार होगा ।

- (xxiii) माईक्रोवेव टावर / स्टेशन, भूकम्प केन्द्र तथा दूरसंचार केन्द्र
- (xxiv) संचार टावर
- (xxv) सरकार या सरकारी एजेंसी द्वारा संविदा अथवा कार्य हेतु अल्पावधि के लिए लगाए जाने वाले तैयार मिश्रण कंक्रीट संयंत्र, वेट मिश्रण संयंत्र, गर्म मिश्रण संयंत्र इत्यादि।
- (xxvi) सर्विस गैरज, बिक्री / प्रदर्शन केन्द्र-सह-सर्विस गैरज का विवरण निम्न अनुसार है:

क्रम	सुविधा का नाम	क्षेत्र (प	एकड़ में)	वाणिज्यिक	अधिकतम	फर्श	पहुंच मार्ग	उंचाई
संख्या	-	न्यूनतम	अधिकतम	घटक	भूतल	क्षेत्र		
					आच्छादन	अनुपात		
1	सर्विस गैरज	0.5	1	शून्य	६० प्रतिशत	1.25	18 मीटर	18
							या सेक्टर	मीटर
							रोड के	
							साथ	
							सर्विस	
							रोड	
2	बिक्री / प्रदर्शन	0.5	2	अनुज्ञेय फर्श	60 प्रतिशत	1.25	18 मीटर	18
	केन्द्र—			क्षेत्र अनुपात			या सेक्टर	मीटर
	सह–सर्विस गैरज			का 10			रोड के	
	बिक्री प्रदर्शन केन्द्र			प्रतिशत			साथ	
							सर्विस	
							रोड	

टिप्पणः *वाणिज्यिक घटक पर फीस तथा प्रभार वाणिज्यिक दरों पर उद्गृहीत किए जाएंगे;

*विद्यमान / पहले से भूमि उपयोग परिवर्तन अनुमित प्राप्त सर्विस गैराज को बिक्री / प्रदर्शन केन्द्र की अनुमित देने हेत् उपरोक्त मानदण्डों को पूरा करने के अध्यधीन विचारा जाएगा।

(xxvii) धर्म कांटा

(xxviii) कोई अन्य उपयोग, जिसे सरकार लोकहित में विनिश्चित करे।

IX बिल्कुल निषिद्ध उपयोग

उचित अनुज्ञप्ति के बिना पैट्रोलियम और अन्य प्रज्जवलनीय सामग्री का भंडारण

परिशिष्ट-1

सूचना प्रौद्योगिकी उद्योग के स्कोप / परिभाषा में सिम्मिलित किए गए उद्योगों की श्रेणियां

(क) कम्प्यूटर डिवाईसिज के अन्तर्गत :

डैस्क्टाप

पर्सनल कम्पयूटरर्स

सरवर्स

वर्क स्टेशन

नोडस

टरमिनलस

नैटवर्क पी.सी.

होम पी.सी.

लैपटॉप कम्पयूटरर्स

नोट बुक कम्पयूटरर्स

पामटॉप कम्पयूटरर्स / पी.डी.ए.

(ख) नैटवर्क कंट्रोलर कॉर्ड / मेमोरी के अन्तर्गत:

नैटवर्क इन्टरफेस कार्ड (एन.आई.सी.)

एडोप्टर इथरनेट / पी.सी.आई. / ई.आई.एस.ए. / कोम्बो / पी.सी.एम.आई.सी.ए.

एस.आई.एम.एम.मेमारी

डी.आई.एम.एम.मेमोरी

सैन्ट्रल प्रोसैंसिग यूनिट(सी.पी.यू.)

कन्ट्रोलर एस.सी.एस.आई. / ऐरे

प्रोसैसर का प्रौसेसर / प्रोसैसर पावर मोडयूल / अपग्रेड

(ग) स्टोरेज यूनिटस के अन्तर्गत:

हार्ड डिसक ड्राईवस / हार्ड ड्राईवस

आर.ए.आई.डी. डिवाईसिस एवं उसके कन्ट्रोलर

फलोपी डिस्क ड्राईव

सी.डी.रोम डाईव

टेप ड्राईवस डी.एल.टी. ड्राईवस / डी.ए.टी.

आपटिकल डिस्क ड्राईव

अन्य डिजीटल स्टोरेज डिवाईज

(घ) अन्य :

की बोर्ड

मोनीटर

माऊस

मल्टीमीडिया किट्स

(ड.) प्रिन्टर तथा आऊटपुट डिवाईसिस के अन्तर्गत :

डोट मैट्रिक्स

लेजरजेट

इन्कजैट

डेस्कजैट

एल.ई.डी. प्रिन्टर्स

लाईन प्रिन्टर्स

प्लाटर्स

पास बुक प्रिन्टर्स

(च) नेटवर्किंग उत्पाद के अन्तर्गतः

हब्ज

रूटर्स

स्विचिस

कोन्सनट्रेटर्स

ट्रांसरिसिवर्स

(छ) सोफटवेयर के अन्तर्गत:

एप्लीकेशन्स साफटवेयर

आपरेटिंग सिस्टम

मिडल वेयर / फर्म वेयर

(ज) कम्पयूटर सिस्टम के लिए लगने वाली पावर सप्लाई के अन्तर्गत :

स्विच मोड पावर सप्लाई

अनइन्टरप्टिड पावर सप्लाई

(झ) नेटवर्किंग / केबलिंग तथा उससे संबंधित उपकरण :

(सूचना प्रौद्योगिकी उद्योग से संबंधित)

फाईबर केबल

कोपर केबल

केबल्स

कनैक्टर्स, टरिमनल ब्लाक

जैक पैनल्स, पैच कोर्ड

माऊटिंग कोर्ड / वायरिंग ब्लाक

सरफेस माउंट बक्से

(ञ) कन्ज्यूमेबल्स के अन्तर्गत :

सी.डी.रोम / कम्पैक्ट डिस्क

फलोपी डिस्क

टैप्स डी.ए.टी. / डी.एल.टी.

रिबन्स

टोनर्स

इन्कजैट कारटेजिस

आऊटपुट डिवाईसिस को लगने वाली इंक

(ट) इलैक्ट्रोनिक कम्पोनेन्ट :

प्रिंटिड सर्किट बोर्ड / पापुलेटिड पी.सी.बी.

प्रिंटिड सर्किट बोर्ड / पी.सी.बी.

ट्रांजिस्टर्स

इन्टैग्रेटिड सर्किट्स/आई.सी.

डायोड्स / थाईरिस्टर / एल.ई.डी.

रेसिस्टर्स

केपेसिटर्स

स्विचिस (ऑन/ऑफ, पुश बटन, रोकर्स इत्यादि)

प्लगस / सोकेट्स / रिलेज

मेगनेटिक हेड्स, प्रिन्ट हैड्स

कनेक्टर

माईक्रोफोन्स / स्पीकर्स

फयूजिस

(ठ) टैलीकम्यूनिकेशन इक्वीपमेन्ट के अन्तर्गत :

टैलीफोन

विडियो फोन

फेसी माईल मशीन / फैक्स कार्ड

टैली प्रिन्टर्स / टैलेक्स मशीन

पी.ए.बी.एक्स. / ई.पी.ए.बी.एक्स. / आर.ए.एक्स. / एम.ए.एक्स. टैलीफोन एक्सचैंज

मल्टीप्लेक्सर्स / म्यूजिस

मोडम्स

टैलीफोन आन्सरिंग मशीन

टैलीकम्यूनिकेशन्स स्वीचिंग एपरेटर्स

एन्टेना तथा मास्ट

वायरलैस डेटाकोम इक्वीपमेन्ट

रिसीविंग इक्वीपमेन्ट लाईक पेजर्स, मोबाईल / सैल्यूलर फोन इत्यादि

वी.एस.ए.टीज.

वीडियो कोनफोरेंसिंग इक्वीपमेन्ट'

वीडियो एवं डिजिटल सिंगनलिंग के लिए लगने वाले सैट टाप बक्से के अन्तर्गत

(ढ) सूचना प्रौद्योगिकी को समर्थ बनाने वाली सेवायें वह व्यवसायिक किया तथा सेवायें है जिसके अन्तिम उत्पाद / सेवायें जिनको :

- भारत से बाहर वितरित करने के लिए
- संचार—जाल के लिए वितरित करने के लिए; तथा
- या तो बाहरी ठेके (बाहरी स्त्रोत) या उस कम्पनी के सुदूर गौण द्वारा उपलब्ध किया हुआ (बाहर अवस्थित

टिप्पण :--

सेवाएं जो इनमें शामिल नहीं हैं, :

- सुदूर उत्पादन / विनिर्माण इकाइयां
- कम्पनियों के निगमित कार्यालय अथवा उनकी स्थानीय शाखाएं
- इन्टरनैट पर वास्तविक व्यवसाय

निम्नलिखित सेवाएं जो उपरोक्त दिये गये मानदण्ड पूर्ण करती हैं, सिम्मिलित होंगी:

- (i) बैंक ऑफिस आप्रेशन्स
- (ii) काल सैन्टरज़
- (iii) कोन्टैन्ट डिवैल्पमैन्ट अथवा एनीमेशन
- (iv) डाटा प्रोसैसिंग
- (v) अभियान्त्रिकी तथा रचना
- (vi) ज्योग्राफिक इन्फोरमेशन सिस्टम सर्विसिज
- (viii) मानव संसाधन सेवायें
- (ix) बीमा दावा प्रोसेसिंग
- (x) लीगल डाटा बेस
- (xi) मैडीकल ट्रान्सक्रिप्शन
- (xii) पे-रोल
- (xiii) सुदूर रख-रखाव
- (xiv) राजस्व लेखाकरण
- (xv) वैब-साईट सर्विसेज

अपूर्व कुमार सिंह, प्रधान सचिव, हरियाणा सरकार, नगर तथा ग्राम आयोजना विभाग।

HARYANA GOVERNMENT

TOWN AND COUNTRY PLANNING DEPARTMENT

Notification

The 17th July, 2019

No. C.C.P.(N.C.R.)/DDP/RR/2019/1432.— In exercise of the powers conferred by sub-section (4) of section 5 of the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963), the Governor of Haryana publishes the following Draft Development Plan 2031, A.D. for the controlled area around Raipur Rani along with restrictions and conditions, given in Annexure 'A' and 'B' proposed to be made applicable to the controlled areas specified in Annexure 'B'.

Notice is hereby given that the Draft Development Plan shall be taken into consideration by the Government on or after expiry of a period of thirty days from the date of publication of this notification in the Official Gazette together with objections and suggestions, if any, which may be received in writing by the Director, Town and Country Planning Department, Haryana, as addressed to Chief Co-coordinator Planner, (NCR) office, First Block, 3rd Floor, HUDA Complex, sector-6, Panchkula from any person with respect to this Draft Development Plan, before the expiry of the period so specified.

Drawings

- Existing Land Use Plan Drawing No. DTP (P) 1063/2008, dated the 5th February, 2008.
- 2 Draft Development Plan Drawing No. DTP (P)1442/2018, dated the 15th January, 2018.

ANNEXURE-A

Explanatory Note on the Draft Development Plan-2031 A.D. for Controlled Area Raipur Rani, District Panchkula

(i) INTRODUCTION:

Consequent upon the upcoming developments in the region i.e. establishment of Information Technology Park in Chandigarh and Panchkula, development of adjoining areas of Punjab (in Dera Bassi as well as in Zirakpur), upgradation of Chandigarh Domestic Airport to International Airport, project for widening of NH-344 for faster connectivity, the area in and around RaipurRani has experienced large scale socio-economic and physical development. Moreover, due to saturation of Panchkula Urban Estate and better connectivity with the other parts of Haryana, this area is experiencing the large scale immigration from outside the region, resulting in pressure on the existing infrastructure and haphazard development to meet the demand of housing and other associated activities. Accordingly, in order to have check over the unregulated development and to provide essential infrastructure, the need has been felt for developing the area in a planned manner.

The controlled area is bifurcated by the Scheduled Road-33 passing through this village and is bounded by agricultural fields on all sides. The village Raipur Rani functions as a Block headquarter as well as nodal settlement for the other rural settlements in this area and are situated at a distance of 33 kilometers from Panchkula, 43 kilometers from Chandigarh towards South-East. Apart from above, it is located at a distance of 20 kilometers from National Highway-152 passing through Derabassi, which the nearest urban settlement of Punjab State. The nearest railway station, from this area, is also located in Derabassi. As per Industrial and Investment Policy-2011 of the State, this area falls in the category of Intermediate Development Block. The abadi of village Raipur Rani is situated adjacent to Scheduled Road-33 at latitude of 30° 34' 57" North and Longitudes 77° 01' 13" East. The industrial activities in this town are basically Agro-based, however after development of this area in a planned manner, development of Kot Behla – Alipur Urban Complex in Haryana and Free Enterprise Zone in adjoining areas of Raipur Rani and Punjab, this region is expected to experience large scale transformation in its functional character. In order to cater the future demand of Raipur Rani, an additional area 281.79 hectare has been added in the form of urbanisable area to accommodate 25,000 additional populations.

The urban settlement will have efficient and sustainable infrastructure and amiable environment for living by preserving natural trails, forest, parks, sport centres, holistic living practices. The city will provide high quality infrastructure to cater both the business and personal needs of the residents. Irrigation Department, Haryana has reported this area as flood prone area therefore, in order to protect the urbanisable area from flood, a bundh along Dangri river has been proposed.

(ii) PHYSIOGRAPHY

The area is normally plain having slope from North to South. The land of this area is fertile and the ground water table is at 150 feet approximately.

(iii) AVAILABILITY OF INFRASTRUCTURE

(a) Utilities

At present Electricity is being supplied from existing 66 KV Sub-Station at Raipur Rani. The water supply is provided from a Tubewell installed by Public Health Department. Presently, the water is being supplied @ 55 liters per capita per day. Presently, no Sewerage System exists in the area. The open drains are constructed along streets in the village abadies to drain out the storm water.

(b) Social Infrastructure

There are 6 Primary Schools, 3 Middle Schools and 2 Secondary Schools to provide educational facilities. There is one Primary Health Centre to cater to medical requirements of the area.

(iv) ECONOMIC BASE OF THE TOWN / FUNCTIONAL STATUS: -

The economic base of village Raipur Rani and other rural settlements falling in this Controlled Area is mainly Agriculture. The main crops cultivated here are wheat, rice and maize. The local market near existing Bus Stand at Raipur Rani cater to needs of the adjoining rural settlements also. In addition, some small scale industries like rice sheller, flourmill, agriculture tools and furniture etc. and some poultry farms exist in this area.

(v) POPULATION / DEMOGRAPHY: -

Since the population of village Raipur Rani is increasing rapidly due to its locational advantages and its fast connectivity with the surrounding areas. The population of village Raipur Rani has increased in 3 folds with an average decadal growth of 30% since 1961 to 2001. Keeping in view the previous decadal growth and development potential of this area, the population of Raipur Rani it expected to increase upto 34,000 in the year 2031 with a growth rate of 95% for the decadal year 2021 and 2031.

(vi) EXISTING TRANSPORTATION NET WORK:

This area has better connectivity with the other parts of the State through Scheduled Road-33 passing through it. Moreover, connectivity through National Highway No. 344 and the railway line is also available at a distance of 16 kilometers at Derabassi in Punjab. Thus, the area is well linked with the other parts of the State as well as the country.

(vii) NEED FOR DECLARATION OF CONTROLLED AREA:

In year 2006, the Controlled area Raipur Rani was notified in order to avoid haphazard and irregular development and to provide channelises urban growth. Approximately 1077.75 Hectares of area was declared as the Controlled Area vide Haryana Government, Town & Country Planning Department, Notification No. CCP (NCR)/PKL/R.R /CA/ 2006/3047, dated the 4thOctober, 2006 which was published in the Haryana Government Gazette dated the 4th October, 2006.

(viii) PROPOSALS:

The village abadi of controlled area, about 9,028 persons would be accommodated with density of 282 persons per Hectare in the existing village settlement and the remaining population along with migrated population of 25,000 persons would be accommodated in the residential area being proposed over an area of 95.96 Hectares with density of 250 persons per Hectares. The above proposed migrated population is expected from the rural hinterland as well as from the tricity of Chandigarh-Panchkula-Mohali, which is having the residential accommodation at exceptionally higher rates beyond the reach of general public and being located only at a approximate distance of 30 kilometers from the proposed International Airport at Chandigarh will play key role in attracting huge influx of population from other areas. In addition, this urban centre would also assist in ever increasing pressure of migrant population in the tricity.

(ix) LAND USE PROPOSALS:

Areas of 281.79 Hectares have been proposed as urbanisable area with the gross town density of 122 persons per Hectares and net residential density of 250 persons per Hectare. Out of total 1077.75 Hectare of Controlled Area, the land use proposals for the Draft Development Plan covers an area of 281.79 Hectare. The Government has notified Affordable Group Housing Policy, New Integrated Licensing Policy (NILP), and Deen Dayal Jan Awas Yojna assigning a specific population density under these schemes. In addition, the Department is also taking 20% Group Housing component in residential sector over and above the sector density. Therefore, population as well as density of these areas of the town will increase.

The detailed break-up of the proposed land uses within the Controlled Area is as below:

TABLE-III: Land Use Proposals

Serial Number	Land Use		% to total area(Area in percentage)
1	Residential	95.96	34.05
2	Commercial	13.77	4.89

3	Industrial	30.07	10.67
4	Transport and Communication	61.65	21.88
5	Public Utilities	13.64	4.84
6	Public and Semi Public	15.72	5.58
7	Green belt and Open Spaces	50.98	18.09
	Total	281.79	100.00

Note:- Total Proposed Urbanisable area= 281.79 + 32.074 = 313.864 hectare, Town Density of 109.72 DESCRIPTION OF LAND USES

1. RESIDENTIAL:

To accommodate the population of 34,000 persons, residential sectors no. 1,9 and 10 over an area of 95.96 hectare have been proposed with proposed density of 250 persons per Hectare. Every residential sector shall be developed to the sector density indicated in the drawing and in addition to it, the density as prescribed in the new integrated licensing policy (NILP), affordable group housing policy, Deen Dayal Jan Awas Yojna (DDJAY), 20% group housing component policy will also be applicable in a residential sector.

In addition to above, the following provisions have also been made in the development plan.

- (a) The area for infrastructure shall be provided in the residential sectors to meet out the requirement of the projected population.
- (b) The minimum width of the roads in a residential colony/sector shall not be less than 12 meters or as per the applicable policies.
- (c) The minimum area for parks /open spaces in residential colony/sectors shall be planned in such a manner that it shall meet the minimum norms of 2.5 sq. meters per person.

2. **COMMERCIAL**:

The commercial activities would not only cater to the needs of existing as well as projected population of this area but also to the population of hinterland. The City Centre, in Sector-8 over an area of 13.77 hectare has been proposed for retail trade, whole sale trade, offices and Banks etc. and existing Grain market over an area of 7.08 Hectare.

3. INDUSTRIAL:

An area of 30.07 hectare (approx.) has been proposed in Sector-5. In this industrial zone, only non-polluting industries would be allowed.

4. TRANSPORT AND COMMUNICATION:

Presently the area is connected by link roads through Scheduled Road-33. The urbanization proposals have been bounded by a 45 meters wide peripheral road, while sector dividing roads have been proposed with 30 meters width. Moreover, Transport and Communication Zone have also been proposed in Sector-6 over an area of 7.40 hectare. The total area under this zone is 61.65 hectare approximately.

The classification of proposed roads is as follows:

Serial	Classification	Land Reservation
Number		
(i)	V-1	45M. Wide Peripheral Road with 30M Wide Green Belt towards outer
		sides.
(ii)	V-2	SR-33 Existing Road with 30M wide Green Belt on both sides.
(iii)	V-3	30M Wide Sector Dividing Road
(iv)	V-4	Existing Road to be widened up to 30M.

Width and alignment of other roads shall be as per sector plans or as per approved layout plans of colonies.

5. PUBLIC UTILITY:

An area approximate 13.64 hectare has been proposed for public utility in sector-4 to meet out the future need of the proposed population.

6. PUBLIC AND SEMI PUBLIC USE:

To provide the educational, cultural, religious, institutional, medical and health facilities, an area of 15.72 hectare has been proposed in Sector-2.

7. OPEN SPACE:

A 30 meters wide restricted green belt has been proposed on both sides of the existing Scheduled Road-33. An area of 48.44 hectare (approximately) falls under this green belt. In addition, 30 meters wide green

buffer has also been proposed on outer sides of Peripheral Road. Further, the town level open spaces have been proposed in Sector 3 and 7 (part).

8. AGRICULTURE ZONE:

The rest of the area i.e. 767.88 hectare, surrounding the urbanization proposals within the Controlled Area would remain as Agriculture Zone. This zone will, however, not eliminate the essential building activities within this area, such as extension of existing village contiguous to abadi-deh if undertaken as a project approved or sponsored by the Government and other ancillary facilities necessary for the maintenance and improvement of agriculture land.

ZONING REGULATIONS:-

The legal sanctity to the proposal regarding land use is being given to the effect by a set of zoning regulations (Annexure B) which form a part of this development plan. These regulations will govern the change of land use and standards of development. They also very elaborately detail out allied and ancillary uses which will be permitted in the various major land uses and stipulate that all change of land use and development shall be in accordance with the details shown in the master plan thereby ensuring the preparation of detailed sector plans for each sector to guide the development and enforce power controls.

ANNEXURE - B

Zoning Regulations

Governing use and development of land in the controlled area around Raipur Rani as shown in Drawing No. DTP (P) 1442/2018, dated the 15th January, 2018.

I General

- 1. These zoning regulations forming part of the Draft Development Plan for the controlled areas around Raipur Rani shall be called zoning regulation of Draft Development Plan for the controlled areas.
- 2. The requirements of these regulations shall extend to the whole of the area covered by the Draft Development Plan and Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963) and the rules framed there under.

II Definitions: -

In these regulations:

- (a) "Approved" means approved by the competent authority;
- (b) "Building Code" means, the Haryana Building Code 2017;
- (c) "Building rules" means the rules contained in part VII of the rules;
- (d) "Drawing" means Drawing No. DTP (P)1442/2018, dated the 15th January, 2018.
- (e) **"Floor Area Ratio (FAR)"** means a quotient obtained by dividing the multiple total covered area of all floors and hundred, by the area of plot i.e.

Floor Area Ratio = $\underline{\text{total covered area x}} 100$

Plot area

For the purpose of calculating FAR, cantilevered, permitted roof projections, lift room, mumty, balcony, basement or any floor if used for parking, services and storage, stilt area (unenclosed) proposed to be used for parking/ pedestrian plaza only, open staircase (without mumty), terrace with or without access, fire staircase, atrium, water tank, open courtyard of permitted size shall not be counted towards FAR:

Provided that, area under shaft, chutes, lift well and staircase from stilt to next floor shall be counted towards FAR only at once on ground floor:

Provided further that in case the ventilation shaft area is more than three square metres, it shall not be counted in FAR;

- (f) **'Fuel Station'** means the fuel filling station providing retail supply of fuel for automobiles which shall include petrol pumps, CNG station, bio fuels, charging station, battery providing stations etc;
- (g) **"Group Housing"** means a building designed and developed in the form of flats for residential purpose or any building ancillary to group housing;
- (h) "Light Industry" means an industry not likely to cause injurious or obnoxious noise, smoke, gas, fumes, odours, dust, effluent and any other nuisance to an excessive degree and motivated by electric power;

- (i) "Local Service Industry" means an industry, the manufacture and product of which is generally consumed within the local area, for example bakeries, ice-cream manufacturing, aerated water, Atta Chakies with power, laundry, dry-cleaning and dyeing, repair and service of automobile, scooters and cycles, repair of house hold utensils, shoe-making and repairing, fuel depot etc. provided no solid fuel is used by them;
- (j) "Medium Industry" means all industries other than 'Light Industry' and Local Service Industry and not emitting obnoxious or injurious fumes and odours;
- (k) "Extensive Industry" means an industry set up with the permission of the Government and in extensive employing more than 100 workers and may use any kind of captive power of fuel provided they do not have any obnoxious features;
- (l) "Heavy Industry" means an industry to be set up in public or semi-public or private sector with the permission of the Government (the cost of plant, machinery etc. as defined in the industrial policy of the Government).
- (m) "Obnoxious or hazardous Industry" means an industry set up with the permission of the Government and is highly capital intensive associated with such features as excessive smoke, noise, vibration, stench, unpleasant or injurious effluent, explosive inflammable material etc. and other hazards to the health and safety of the community;
- (n) "Material Date" means the date of publication of notification of various controlled area declared as under: -

Serial Number	Controlled area and notification No.	Material date		
1	Controlled Area notified vide Haryana Government Gazette	4th October, 2006		
	notification No. CCP (NCR)/PKL/R.R/CA(B) 2006/3047 dated the			
	4th October, 2006 published on 4th October, 2006.			

- (o) "Non-conforming use" in respect of any land or building in a controlled area means the existing use of such land or building which is contrary to the major land use specified for that part of the area in the development plan;
- (p) "Public Utility Service Building" means any building required for running of public utility services such as water-supply, drainage, electricity, post and telegraph and transport and for any municipal services including a fire station;
- (q) 'Rules' means the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Rules, 1965 and the rules framed under the Haryana Municipal Committee Act, 1973.
- (r) 'Sector Density' and 'Colony Density' and 'Town Planning Scheme Density' shall mean the number of persons per hectares in sector area, colony area and Town planning scheme as the case may be.
- (s) **'Sector Area'** and **'Colony Area'** and 'Town Planning Scheme area' shall mean the area of the sector or colony or of the scheme as bounded within the major road system shown on the drawing and /or as shown in the approved layout of the sector/ colony/scheme;

Explanation:-

- (1) In this definition the 'Sector Area' or 'Colony Area' or 'Town Planning Scheme Area' shall mean the area of the Sector or of Colony or of Town Planning Scheme as shown on the drawing or on the approved layout plan of the Colony/Sector/ Town Planning Scheme which will be excluding the area unfit for building development within the sector or the colony or the scheme as the case may be;
- (2) Benefit of 50% of the area falling under major roads and their adjoining green belts, if any, shall be allowed for plotable area/Floor area ratio (FAR) in case of plotted/group housing colony;
- (3) In the layout plan of Town Planning Scheme, colony or sector, other than industrial scheme/colony/sector, the land reserved for roads, open space, schools, public and community building and other common uses shall not be less than 45% of the gross area of the land under the Town Planning Scheme/colony/sector;
- (4) For the purposes of calculation of sector density or colony density, it shall be assumed that 55 percent of the sector area or colony area will be available for residential plots including the area under Group Housing and that every building plot shall on the average contain three dwelling units each with a population of 4.5 persons per dwelling unit or 13.5 persons building plot or as incorporated in the zoning plan of the colony/group housing complex. In the case of shop-cumresidential plot, however, only one dwelling unit shall be assumed;

- (5) Notwithstanding above, the projects approved under specific policy like New Integrated Licensing Policy; FAR and Density shall be the governing parameters instead of plotable area.
- (t) "Site Coverage" means ratio expressed in percentage between the area covered by the ground floor of building and the area of the site;
- (u) The term "Act", "Colony" "Colonizer" "Development plan", "Sector" Scheme' and "Sector Plan" shall have the same meaning as assigned to them in the Punjab Scheduled Roads and Controlled areas Restriction of Unregulated Development Act, 1963 (Punjab Act 41 of 1963) and rules, 1965 and the Haryana Municipal Act, 1973 (24 of 1973) and the rules framed thereunder.
- (v) "Farm House" means a house constructed by the owner of a farm at his land for the purpose of:-
 - (i) dwelling unit i.e. main use; and
 - (ii) farm shed i.e. ancillary use.

Notes:-

- (1) The construction of the farm house shall be governed by the restrictions given under clause XIX regarding "provision of farm house outside abadi-deh in rural/agricultural zone";
- (2) The farm sheds shall be governed by the restrictions mentioned in clause XIX regarding building control and site specifications;
- (w) "Ledge or Tand" means a shelf-like projection, supported in any manner whatsoever, except by means of vertical supports within a room itself but not having projection wider than one meter;
- (x) "Loft" shall means an intermediate space between two floors on a residual space with maximum height of 1.5 metres and which is constructed or adopted for storage purposes only;
- (y) "Mezzanine Floor" means an intermediate floor, between two floors, with area restricted to ½ (half) of the lower floor and with a minimum height of 2.3 metres and shall not be lower than 2.3 metres (clear height) above floor level;
- (z) "Subservient to Agriculture" means development and activities, which are required to assist in carrying out the process of agriculture such as tubewells, pump chambers, wind mills, irrigation's drains, pucca platforms, fencing and boundary walls, water hydrants etc.
- (za) "Rural Industries Schemes" means industrial unit, which is registered as rural industries schemes by the Industries Department;
- (zb) **"Small Scale Industries"** means industrial unit, which is registered as small scale industries by the Industries Department;
- (zc) "Agro based industries" means an industrial unit, which uses foodgrains, fruits or agro waste as a raw material; and
- (zd) "Information Technology Industrial Units" means the categories of industries included in the Annexure to the Government of Haryana Information Technology Policy, 2000 and in Appendix-I to this notification and/or, as may be defined by the Government of Haryana from time to time.
- (ze) "Cyber Park" / "Information Technology Park" means an area developed exclusively for locating software development activities and Information Technology Enabled Services wherein no manufacturing of any kind (including assembling activities) shall be permitted;
- (zf) "Cyber City" means self contained intelligent city with high quality of infrastructure, attractive surrounding and high speed communication access to be developed for nucleating the Information Technology concept and germination of medium and large software companies/Information Technology Enabled Services where in no manufacturing units may be allowed; and
- (zg) "Green Belt" shall mean, strips of land along sector/arterial road shown in the development plan primarily meant for the widening of the sector/arterial road in future.
- (zh) Any other term shall have the same meaning as assigned to it in the Punjab Scheduled Roads and Controlled Areas Restriction of Unregulated Development Act, 1963, (Punjab Act 41 of 1963) and the rules 1965 and the Haryana Municipal Act, 1973 (24 of 1973) and the rules framed there under;

III. (1) MAJOR LAND USES/ZONE

- (i) Residential zone
- (ii) Commercial zone

- (iii) Industrial zone
- (iv) Transport and communication zone
- (v) Public Utility Zone
- (vi) Public and semi public zone (institutional zone)
- (vii) Open spaces zone
- (viii) Agriculture zone
- (2) Classification of major land uses is according to Appendix A.

IV. DIVISION INTO SECTOR

Major land uses mentioned at serial nos. (i) to (vii) in zoning regulation-III above, which are land uses for building purposes, have been divided into sectors as shown, bounded by the major road reservations and each sector shall be designated by the number as indicated on the drawing.

V. DETAILED LAND USES WITHIN MAJOR USES

Main, ancillary and allied uses, which are subject to the other requirements of these regulations and of the rules, may be permitted in the respective major land uses zones are listed in Appendix B sub-joined to these zoning regulations.

VI. SECTORS NOT RIPE FOR DEVELOPMENT

Notwithstanding the reservation of various sectors for respective land uses for building purposes, the Director may not permit any changes in their land use or allow construction of building thereon from consideration of compact and economical development of the controlled area till such time as availability of water supply, drainage arrangement and other facilities for these sectors are ensured to his satisfaction.

VII. SECTORS TO BE DEVELOPED EXCLUSIVELY THROUGH GOVERNMENT ENTERPRISES

Government may notify any sector for development exclusively by it or by its agencies, in which case, no further permission for change of land use or grant of licence shall be permitted in such sectors.

VIII. LAND RESERVATIONS OF MAJOR ROADS

(1) Land reservation for major roads marked in the Drawing shall be as under :-

Serial	Classification	Land Reservation
Number		
(i)	V-1	45M. Wide Peripheral Road with 30M Wide Green Belt outer sides.
(ii)	V-2	SR-33 Existing Road with 30M wide Green Belt on both sides.
(iii)	V-3	30M Wide Sector Dividing Road
(iv)	V-4	Existing Road to be widened up to 30M.

- (2) Width and alignment of other roads shall be as per sector plans or as per approved layout plans of colonies.
- (3) Benefit of tradable Floor Area Ratio, may be allowed against licences granted for the land falling under sector road or green belt and open space zones in accordance with specified policies.

IX. Non-conforming uses either existing or having valid Charges of land use permission:-

- (1) With regard to the existing industries located in the zones other than conforming-use zone in the Development Plan, such non-conforming uses shall be allowed to continue for a fixed period to be determined by the Director, but not exceeding ten years; provided that the owner of the building concerned:
 - (a) Undertakes to pay to the Director, as determined by him the proportionate charges, toward, the external development of the site as and when called upon by the Director to do so in this behalf;
 - (b) During the interim period makes satisfactory arrangements for the discharge of effluent to the satisfaction of the Director.
 - (c) Shall not be allowed to expand the existing project within the area of non conforming use.
- (2) With regard to the projects having valid change of Land use permissions, and located in the zones other than conforming use zone in the Development Plan, such non-conforming uses shall be allowed to continue, provided that the owner of the building concerned:

- (a) Undertakes to pay to the Director, as determined by him the proportionate charges towards the external development of the site as and when called upon by the Director to do so in this behalf; and,
- (b) During the interim period makes satisfactory arrangements for the discharge of effluent to the satisfaction of the Director.

X. DISCONTINUANCE OF NON CONFORMING USES

- (1) If a non-conforming use of land has remained discontinued continuously for a period of two years or more, it shall be deemed to have terminated and the land shall be allowed to be re-used or re-developed only according to the conforming use.
- (2) If a non-conforming use building is damaged to the extent of 50 percent or more of its re-production value by fire, flood, explosion, earthquake, war, riot or any other natural calamity, it shall be allowed to be re-developed only for a conforming use.
- (3) After a lapse of period fixed under clause IX, the land shall be allowed to be redeveloped or used only for conforming use.
- (4) After a lapse of period fixed under clause IX(I), the land shall be allowed to be redeveloped or used only for conforming use.

XI. THE DEVELOPMENT TO CONFORM TO SECTOR PLAN AND ZONING PLAN

Except as provided in regulation IX, no land within major land use shall be allowed to be used and developed for building purposes unless the proposed use and development is according to the details indicated in the sector plan and zoning plan or the approved colony plan in which the land is situated.

XII. INDIVIDUAL SITE TO FORM PART OF APPROVED LAYOUT OR ZONING PLAN

No permission for erection or re-erection of building on a plot shall be given unless-

- (i) the plot forms a part of an approved colony or the plot is in such area for which relaxation has been granted as provided in regulation XVII; and
- (ii) the plot is accessible through a road laid out and constructed up to the situation of the plot to the satisfaction of the Director.

XIII. MINIMUM SIZE OF PLOTS FOR VARIOUS TYPES OF BUILDINGS

(1) The minimum size of the plots for various types of uses shall be as below:-

Sr.	Land use		Size
No.			
(i)	Residential plot	:	50 Square meters
(ii)	Residential plot in subsidized industrial housing or slum dwellers housing scheme approved by the Government	:	35 Square meters
(iii)	Shop-cum-residential plot	:	100 Square meters
(iv)	Shopping booths including covered corridor or pavement in front	:	20 Square meters
(v)	Local service industry plot	:	100 Square meters
(vi)	Light industry plot	:	250 Square meters
(vii)	Medium industry plot	:	8000 Sqare meters

(2) The area norms for group housing colony, plotted residential colony and commercial colony shall be in the accordance with the policies specified from time to time for residential and commercial development. However, in a case group housing scheme is floated by Haryana Urban Development Authority or any other Government Agency, the size of group housing site shall be as specified in the scheme.

XIV. SITE COVERAGE, HEIGHT AND BULK OF BUILDING UNDER VARIOUS TYPES OF BUILDINGS:-

Site coverage, Floor Area Ratio and height permitted on a specific plot/site shall be governed by the prescribed policy parameters, building code/rules and /or as laid down in the zoning plan of such plot/site.

XV. BUILDING LINES IN FRONT AND REAR OF BUILDINGS:-

These shall be provided in accordance with building code/rules and /or as laid down in the zoning plan of such site.

XVI. ARCHITECTURAL CONTROL:-

Wherever architectural control is considered necessary, every building shall conform to architectural control prepared under clause 6.4 of Haryana Building Code 2017.

XVII. RELAXATION OF AGRICULTURAL ZONE:-

In the case of any land lying in Agriculture zone, Government may relax the provisions of this development plan-

- (a) for use and development of the land into a residential or industrial colony provided the coloniser has purchased the land for the said use and developed prior to the material date and the coloniser secures permission for this purpose as per Rules.
- (b) for use of land as an individual site (as distinct from an industrial colony).

Provided that-

- (i) the land was purchased prior to the material date;
- (ii) the Government is satisfied that the need of the industry is such that it cannot await alternative allotment in the proper zone;
- (iii) the owner of the land secures permission for building as required under the Rules;
- (iv) the owner of the land undertakes to pay to the Director, as determined by him, the proportionate charges as and when called upon by the Director in this behalf and during the interim period makes satisfactory arrangement for discharge of effluent.

Explanation-The word 'purchase' in the regulation shall mean acquisition of full proprietary rights and no lesser title, such as agreement to purchase etc.

XVIII. DENSITY

Every residential sector shall be developed to the sector density indicated in the drawing with 20% variation on either side and in addition to it, the density as prescribed in the New Integrated Licensing Policy, Deen Dayal Jan Awaas Yojna Policy and Affordable Group Housing policy. 20% Group Housing component policy shall also be applicable in a residential sector.

XIX. PROVISION OF FARM HOUSE OUTSIDE ABADI-DEH IN AGRICULTURAL ZONE.

Farmhouses shall be allowed only for bonafide use of landowner(s) provided he does not own a house in any urban area because the real objective for allowing farmhouses in agriculture zone is to meet the housing needs of the farmers on a small portion of the farm so that he can take care of his agriculture produce while living on that farm. Hence, a farm house in agriculture zone, outside abadi-deh may be allowed if the area of the land is 2 acres or more on the following conditions:-

	Size of farm house	Main building of the dwelling unit	Ancillary building of main dwelling unit
(i) Site Coverage	2 Acres minimum but CLU permission for the area falling under road reservation/ proposed road widening as per Development Plan, shall not be considered. However the net area should not be less than 1.5 acres after excluding the area falling under the green belt/restricted belt and falling in Agriculture zone from applied area of 2 acres.	As applicable to residential plot equivalent to 250 sq.yds.	1 percent of the farm (not more than 40 % shall be used for labor/servant quarters)
	Upto 3 acres	As applicable to residential plot equivalent to 375 sq. yds.	-do-
	Upto 4 acres and above	As applicable to residential plot equivalent to 500 sq. yds.	-do-
(ii) Height and	Storey	11 meters, three storeyed	4 meters single storey.

(iii) SET BACK:-

It shall be at least 10 meters away from the edge of the agricultural land on all sides provided that if land attached to the farm house abuts a road, the house shall be constructed with a minimum set back from the edge of the road as under:

Serial Number	Road	Width
(a)	Where the road is bye pass to a Scheduled Road.	100 meters.
(b)	Where the road is a Scheduled Road Plan.	30 meters or a shown in the Development
(c)	Any other road.	10 meters.

(iv) APPROACH ROAD:-

Any revenue rasta/ road is defined in the revenue record.

(v) BASEMENT:-

Basement shall be permitted to the maximum extent of ground floor coverage and uses are permitted as per the Haryana Building Code-2017.

(vi) LEDGE, LOFT AND MEZZANINE FLOOR:-

Ledge, loft and mezzanine floor shall be permitted within the building subject to the restrictions above as well as the restrictions stipulated in the definition given in clause –II of zoning regulations of Development Plan.

(vii) SERVICE WATER SUPPLY AND DRAINAGE:-

- (a) Good potable water supply should be available in the farm for human consumption in case of farm house is built.
- (b) Open sanitary drains or covered drains to be provided to clean the sheds in case of Dairy farms, Drains are to be provided for carrying rain water in case of all buildings.
- (c) Septic tank to be provided for disposal of human and animals waste as per provisions of Rules.
- (d) The distance between the septic tank and open well or tubewell shall be as provided in the Rules.
- (viii) The owner shall be permitted to construct boundary wall around the main dwelling unit and ancillary portion thereof and around remaining area of farm barbed wire fencing shall be allowed.
- (ix) The CLU permission for setting up of farmhouse shall be considered in the area other than over exploited or critical areas as declared by Central Ground Water Board.

Provided that Government may amend the minimum size of the farm for any schemes sponsored by the State Government/State agency for the proper utilization of the agriculture zone.

XX. PROVISIONS OF INFORMATION TECHNOLOGY UNITS AND CYBER PARKS/CYBER CITIES

(i) Location

- (a) Information Technology Industrial Units will be located in Industrial Areas / Industrial Zones only;
- (b) Cyber Parks/Information Technology Parks will be located either in Industrial Areas or Industrial abutting sector roads in the form of integrated development. However, no manufacturing units will be permitted in such parks.
- (c) Cyber Cities:- The location of such a facility will be decided by the Government;

(ii) SIZE

Serial Number	Туре	Size
1	Information Technology Industrial Unit	1 to 5 acres
2	Cyber Park / Information Technology Park	5 to 15 acres
3.	Cyber City	minimum 50 Acres

(iii) MISCELLANEOUS

I Parking

Parking will be as per the provisions of Haryana Building Code 2017 as amended from time to time.

II Other Activities

- (a) Incidental commercial activities like Banks, Restaurants, Insurance Offices etc. shall be permitted subject to restriction of 4% of the gross area of the Cyber Park/Information Technology Park;
- (b) Only 5% of the area of the Cyber City shall be allowed for Group Housing and 4% of the total area of the cyber city shall be permitted for Commercial/Institutional uses;
- (c) No residential plotted development shall be allowed in a Cyber City;
- (d) For a Cyber City Project if allowed in Agricultural /Rural Zone, the entrepreneur shall make the arrangement of water supply and other facilities like sewerage disposal/drainage etc;
- III The Government may impose any other condition as deemed necessary from time to time.

XXI. SETTING UP OF COMMUNICATION TOWERS:-

Permission of Mobile Towers within the controlled area shall be granted as per the policy justification of departments memo dated 10.03.2015 as amended from time to time.

XXII. SAFETY AGAINST SEISMIC HAZARDS:-

As the Development Plan area falls in Seismic zone as per seismic zone map of Indian Standard IS 1893:2002 and hence is considered as High Risk Zone. In order to take care of the same "the whole urban development shall be checked for safety against an intensity "VIII" probability of occurrence, and upgraded for required seismic resistance in building and infrastructure as found necessary".

XXIII. RELAXATION OF DEVELOPMENT PLAN:-

Government may in case of hardship or with a view to save any structure constructed before the material date, relax any of the provisions of the Development Plan on principles of equity and justice on payment of such development charges and on such other conditions as it may deem fit to impose.

APPENDIX A
CLASSIFICATION OF LAND USES

Main code	Sub code	Main group	Sub group
100		Residential	Residential sector on neighborhood pattern
200		Commercial	
	210		Retail Trade
	220		Wholesale Trade
	230		Warehousing and Storage
	240		Office and Banks including Government office
	250		Restaurants, Hotels and Transient Boarding houses including public assistance institutions providing residential accommodation like Dharamshala, Tourist house etc.
	260		Cinema and other places of public assembly on a commercial basis.
	270		Professional establishments
300		Industrial	
	310		Service industry
	320		Light industry
	330		Extensive industry

400		Transport and Communication	
	420		Roads, Road Transport Depots and Parking Areas
	450		Telegraph offices, Telephone Exchanges etc
	460		Broadcasting Station
	470		Television Station
500		Public utilities	
	510		Water Supply installation including treatment plants
	520		Drainage and Sanitary installation including disposal works
	530		Electric power plants substation etc.
	540		Gas Installation and gas work.
	550		Solid waste sites
600		Public and semi public	
	610		Government Administrative Central Secretariat District Offices, Law Courts, Jails, Police Stations, Governors and President's Residence.
	620		Education, Cultural and Religious Institutions
	630		Medical and Health Institutions
	640		Cultural institution like Theatres, Opera Houses etc. of a predominantly non commercial nature
700		Open Spaces	
	710		Sports Grounds, Stadium and Play Grounds
	720		Parks
	730		Green Belts, Garden and other Recreational Uses.
	740		Cemeteries, crematories etc.
	750		Fuel stations and Bus Queue Shelters
	760		Water bodies/ lakes
800		Agricultural land	
	890		Dairy farming

APPENDIX B

The permissible activities given under main land uses shall be allowed in accordance with the policy/parameters approved by the Government and/or at sites as approved by the Competent Authority in the Sector/Colony/Scheme Plan.

I. RESIDENTIAL ZONE

- (i) Residence
- (ii) Social community religious and recreational buildings
- (iii) Public utility buildings
- (iv) Educational buildings and all types of school and college where necessary.
- (v) Health institutions.
- (vi) Cinemas
- (vii) Commercial and professional offices.
- (viii) Retail shops, dhabas and restaurants.

- (ix) Local service industries.
- (x) Fuel stations.
- (xi) Bus stops, tonga, taxi, scooter and auto/rickshaw stand.
- (xii) Nurseries and green houses.
- (xiii) Any other minor needs to ancillary to residential use
- (xiv) Starred hotels
- (xv) Clubs/Community Centres
- (xvi) Communication Towers
- (xvii) Guest/Boarding Houses
- (xviii) Any other use, which the Government may in public interest decide.

II. COMMERCIAL ZONE

- (i) Retail Trade.
- (ii) Wholesale Trade.
- (iii) Warehouses and storages.
- (iv) Commercial offices and banks.
- (v) Restaurant and Transient Boarding Houses including public assistance institutions providing residential accommodation like Dharamshala, Tourist House etc.
- (vi) Cinemas, Hotels, Motels and other places of public assembly like theatres, club, Dramatic Club, etc. run on commercial basis.
- (vii) Professional establishments.
- (viii) Residences on the first and higher floors.
- (ix) Local service industry.
- (x) Public utility buildings.
- (xi) Fuel stations and service garages.
- (xii) Loading and unloading yards.
- (xiii) Parking spaces, bus stops, taxis, tonga, auto/rickshaw stand.
- (xiv) Town parks.
- (xv) Communication Towers
- (xvi) Any other use, which the Government may in public interest decide.

III. INDUSTRIAL ZONE

- (i) Light industry
- (ii) Medium industry
- (iii) Obnoxious and Hazardous Industry
- (iv) Heavy industry
- (v) Service industry
- (vi) Warehouse and storages
- (vii) Parking, loading and unloading area
- (viii) Truck stand/bus stops, taxi, tonga and auto/rickshaw stand
- (ix) Public utility, community buildings, retail shops, banks, dhabas, restaurants, two/three/five star hotels and insurance offices subject to a maximum limit of 3 percent of the total area of the sector as under: -

Serial	Name of	Aı	rea	No. of	Commercial	Maximum	Floor Area	Approach
Number	Facility	Minimum	Maximum	facilities in a sector	component	Ground Coverage	Ratio	Road
1	Dhabas	500 sq. m.	1000 sq m	2	50 sqm	40 %	40%	Minimum 18 metres
2	Restaurants	1000 sq. m.	2000 sqm	2	10 %	30 %	150%	Minimum 18 metres

Serial	Name of	Aı	rea	No. of	Commercial	Maximum	Floor Area	Approach
Number	Facility	Minimum	Maximum	facilities in a sector	component	Ground Coverage	Ratio	Road
3	Two/ Three Star Hotels	1.0 Acre	2.5 Acres	2	15 %	30 %	As per commercial policy	Minimum 24 metres
4	Five Star Hotels	2.5 Acres	4.0 Acres	1	15 %	30 %	As per commercial policy	Sector Dividing Road with the provision of a service road

- (x) Fuel stations and service garages.
- (xi) Liquid Petroleum Gas godowns permitted by the Director.
- (xii) Cyber Parks/Information Technology Parks/ Information Technology Industrial Units
- (xiii) Health Facilities like Hospital, Dispensary, Nursing Home and Clinic as under:

Serial	Name of	Area		No. of	Residential	Maximum	Floor area	
Number	facility	Minimum	Maximum	facilities in a sector	component	ground coverage	ratio	
1	Hospital	2.5 Acres	5.0 Acres	1	15 %	33 %	1.00	
2	Dispensary	1.0 Acre	1.5 Acres	1	15 %	33 %	1.00	
3	Nursing Home	250 sq. m.	500 sq. m.	2	Nil	60 %	1.00	
4	Clinic	250 sq. m.	500 sq. m.	2	Nil	60 %	1.00	

- (xiv) Industrial Colony with a minimum area of 15 acres. The area utilization shall be as per policy issued *vide* ACS, T&CP, Haryana, Chandigarh memo No. Misc.388/PA(RB)/2015/7/16/2006-2TCP dated 01.10.2015 as amended upto date.
- (xv) Communication Towers
- (xvi) Ready mix concrete plant, wet mix plants, hot mix plants
- (xvii) Weighing Bridge
- (xviii) Service Garage, Sale/Display Centre-cum-service garage as under:-

Serial			Commercial	Maximum	Floor	Approach	Height	
Number	facility	Minimum	Maximum	component	ground coverage	Area Ratio	Road	
1	Service Garage	0.5	1	Nil	60%	1.25	Minimum 18 metres or service road along sector road	18 metres
2	Sale/Display Centre-cum- service garage	0.5	2	10% of permissible Floor Area Ratio	60%	1.25	Minimum 18 metres or service road along sector road	18 metres

Note: * The fee and charges on commercial component shall be levied on the commercial rates;

- * Existing/already CLU granted service garages shall be considered for grant of permission for sale/display centre subject to fulfillment of the above norms.
- (xix) Any other use, which the Government may, in public interest decide.

IV. TRANSPORT AND COMMUNICATION ZONE

- (i) Railway yards, railway station and siding
- (ii) Transport Nagar, Roads and Transport depots/Bus stands and parking areas

- (iii) Airports and Air Stations
- (iv) Telephone exchange
- (v) Broadcasting stations
- (vi) Televisions station
- (vii) Agricultural, horticulture and nurseries at approved sites and places
- (viii) Fuel stations and service garages
- (ix) Parking spaces ,bus stop-shelters, taxi, Tonga and auto/rickshaw stands
- (x) Logistics Hubs/Container Yards, Inland Container Depot, Container Freight Station
- (xi) Weighing Bridge
- (xii) Communication Tower.
- (xiii) Warehouses upto a maximum limit of 20% of the total area of the sector.
- (xiv) Dhabas, as per prevailing policy.

V. PUBLIC UTILITIES

- (i) Water supply installations including treatment plants.
- (ii) Drainage and Sanitary installations including sewerage treatment plants and Disposal works.
- (iii) Electric Power plant and sub-station including grid sub-station.
- (iv) Gas installations and Gas works.
- (v) Solid Waste Management Sites

VI. PUBLIC AND SEMI PUBLIC USES ZONE

- (i) Government offices ,Government Administration centers, secretariats and police station
- (ii) Educational, cultural and religious institutions
- (iii) Medical health institutions
- (iv) Civic/cultural and social institutions like theatres, opera houses etc. of predominantly non-commercial nature
- (v) Land belonging to Defence
- (vi) Dhabas, Restaurants as under: -

Serial	Name of	Ar	Area		Commercial	Maximum	Floor	
Number.	Facility	Minimum	Maximum	facilities in a sector	component	Ground Coverage	Area Ratio	
1	Dhabas	500 sq. mtrs.	1000 sq. mtrs.	2	50 sq. m	50 %	40%	
2	Restaurants	1000 sq. mtrs.	2000 sq. mtrs.	2	10 %	30 %	150%	

- (vii) Communication Towers
- (viii) Fuel station
- (ix) Any other use, which the Government may in public interest decide

VII. OPEN SPACES

- (i) Sports ground, stadium and play grounds
- (ii) Parks, green belts, garden and other recreational uses
- (iii) Cemeteries, crematories etc.
- (iv) Fuel stations, bus queue shelter along roads with the permission of Director
- (v) Public utility services like electric grid station, transmission lines, communication line, water supply lines, sewerage lines, drainage lines in the green belts along the scheduled roads and major roads.
- (vi) Water bodies/lakes /water recharge zone.
- (vii) Communication Towers
- (viii) Mela Ground, Multipurpose ground
- (ix) Any other use, which the Government may in public interest decide.

VIII. AGRICULTURE ZONE

- (i) Agricultural, Horticultural, dairy and poultry farming.
- (ii) Village houses within Abadi-deh
- (iii) Farm houses outside abadi-deh subject to restrictions as laid down in zoning regulation XIX
- (iv) Afforestation development of any of the part for recreation
- (v) Expansion of existing village contiguous to abadi-deh if undertaken as a project approved or sponsored by the Central Government or State Government.
- (vi) Milk chilling station and pasteurisation plant
- (vii) Bus Stand and railway station
- (viii) Air ports with necessary buildings
- (ix) Wireless stations
- (x) Grain godowns, storage space at sites approved by the Director
- (xi) Weather stations
- (xii) Land drainage and irrigation, hydroelectric works and tubewell for irrigation
- (xiii) Telephone and electric transmission lines and poles
- (xiv) Mining and extraction operations including lime and brick kilns, stones, quarries and crushing subject to the rules and at approved site
- (xv) Cremation and burial grounds
- (xvi) Fuel station and service garages
- (xvii) Renewable and non-renewable energy power plants.
- (xviii) Liquid Petroleum Gas storage godowns with the approval of the Director
- (xix) Rural Industry Scheme/Small Scale Industrial units shall be allowed subject to fulfillment of the following conditions, provided that the site should not fall within restricted belt notified under the 'Works Defence Act, 1903' around Defence installations, if any:

A. Siting norms			
Zone	Norms		
Low potential zone	Within 2 kms from Urbanisable Zone (excluding the peripheral roads, if proposed along urbansiable boundary) Beyond 2 kms from Urbanisable (excluding the peripheral roproposed along urbansiable boundary)		
	Non-polluting green, category units of any area	Green and orange category units of any area	
B. Approach norms			
Medium and Low Potential zone	Minimum 30 ft wide revenue rasta/public road be considered for grant of CLU permission in agriculture zone for industrial use. However, in case industrial Change of Land Use permission stands granted on 5 karam (27.5 ft) wide revenue rasta/public road, then application for CLU permission on the said road, shall be considered subject to the condition that the project proponent donates 1 karam (5.5 ft) wide strip of the applied land to the Gram Panchayat/Local Authority through Hibbanama/gift deed so as to make the approach 6 karma (33 ft) in front of the applied site.		

(xx) Non polluting Medium and Large Scale Agro-based Industries on Public road/rasta not less than 30 feet wide other than scheduled roads, National Highway and State Highway subject to the condition that site

should not fall within restricted belt around the defence installation as applicable for such installation if any.

(xxi) Dhabas, Banquet Hall, Small Restaurants, Motels, Hotels, Resort and Amusement Park/ Theme Park along National Highway / Scheduled Roads in the area outside restricted/ green belt as under:

Serial Number	Permissible Activity	Area			Maximum Ground	Floor
Number		Minimum	Maximum	Component	Coverage	Area Ratio
1	Dhabas	1000 sq. metres	1 acre	50 Sqmt.	40%	40%
2	Restaurant	2000 sq. metres	1 acre	15%	30%	150%
3	Motel with banquet facilities	2.5 acres	5 acres	15%	30%	150%
4	Resort	4 acres	10 acres	15%	30%	150%
5	Amusement Park/Theme Park	2.5 acres	10 acres	15%	30%	50%

Provided that the access permission is obtained from National Highway Authority of India if the site is located on National Highway, and from Executive Engineer, Public Works (Building and Roads) Department if the site is located on scheduled road.

(xxii) Banquet Hall:

Permissible Zone	Agriculture				
Approach	1. Minimum width of the approach road must be 18 metres.				
	2. The access permission is required from XEN, PWD (B&R) if the site is located on scheduled road.				
	3. Approach from National Highways can be considered, if the site fulfills minimum distance norms from intersection/access and is located on minimum 7 meters wide service road or the applicant submits prior permission of access from NHAI.				
Area Required	Minimum area :- 2.5 acres				
	Maximum area :- 5.00 acres				
Floor Area Ratio	50%				
Ground Coverage	30%				
Conversion Charges	50% of the rates prescribed for commercial use				
Permissible Ancillary uses within FAR	10% of the allowed FAR for Gift shop, STD Booth, Toy Centers and flowers shops etc.				
Parking	Minimum 25% of the site area				

Note: The provision of marriage palace/banquet hall within the municipal limit shall be as per the policy approved by the Department of Urban Local Bodies and as amended from time to time.

- (xxiii) Microwave Towers/Stations, Seismic Centres and Telecommunication Centres
- (xxiv) Communication Towers
- (xxv) Ready Mix Concrete Plants, Wet mix plants, Hot Mix Plants connected with the projects for which contract or work is assigned by Government or Government agency and to be set up on short term
- (xxvi) Service Garage, Sale/Display Centre-cum-service garage as under:
- (xxvii) Weighing Bridge
- (xxviii) Service Garage, Sale/Display Centre-cum-service garage as under:

Serial Number	Name of facility	Area (in acres)		Commercial	Maximum	Floor	Approach	Height
		Minimum	Maximum	component	ground coverage	Area Ratio	Road	
1	Service Garage	0.5	1	Nil	60%	1.25	Minimum 18 metres or service road along sector road	18 metres
2	Sale/Display Centre-cum- service garage	0.5	2	10% of permissible Floor Area Ratio	60%	1.25	Minimum 18 metres or service road along sector road	18 metres

Note: * The fee and charges on commercial component shall be levied on the commercial rates;

* Existing/already CLU granted service garages shall be considered for grant of permission for sale/display centre subject to fulfillment of the above norms.

(xxix) Any other use, which Government may in Public Interest, decide

IX. Uses strictly prohibited:

Storages of petroleum and other inflammable material without proper license.

APPENDIX -1

Categories of Industries included in the scope / definition of Information Technology Industry

(A) Computing Devices including

Desktop

Personal Computer

Servers

Work-station

Nodes

Terminals

Network P.C.

Home P.C.

Lap-top Computers

Note Book Computers

Palm top Computer/PDA

(B) Network Controller Card/ Memories including

Network Interface Card (NIC)

Adaptor Ethernet /PCI/EISA/Combo/PCMICA

SIMMs Memory

DIMMs Memory

Central Processing Unit (CPU)

Controller SCSI/Array

Processors Processor/Processor Power Module/Upgrade

(C) Storage Units including

Hard Disk Drives/Hard Drives

RAID Devices and their Controllers

Floppy Disk Drives

C.D. ROM Drives

Tape Drives DLT Drives/DAT

Optical Disk Drives

Other Digital Storage Devices

(D) Other

Key Board

Monitor

Mouse

Multi-media Kits

(E) Printers and Output Devices including

Dot matrix

Laserjet

Inkjet

Deskjet

LED Printers

Line Printers

Plotters

Pass-book Printers

(F) Networking products including

Hubs

Routers

Switches

Concentrators

Trans-receivers

(G) Software including

Application Software

Operating system

Middleware/Firmware

(H) Power supplies to Computer Systems including

Switch Mode Power Supplies

Uninterrupted Power supplies

(I) Networking/Cabling and related accessories

(related to IT Industry)

Fibre Cable

Copper Cable

Cables

Connectors, Terminal Blocks

Jack Panels, Patch Cord

Mounting Cord/Wiring Blocks

Surface Mount Boxes

(J) Consumables including

C.D.ROM /Compact Disk

Floppy Disk

Tapes DAT/DLT

Ribbons

Toners

Inkjet Cartridges

Inks for Output devices

(K) Electronic Components

Printed Circuit Board/Populated PCB

Printed Circuit Board/PCB

Transistors

Integrated Circuits/ICs

Diodes/Thyristor/LED

Resistors

Capacitors

Switches (On/Off, Push button, Rocker, etc.)

Plugs/sockets/relays

Magnetic heads, Print heads

Connectors

Microphones/Speakers

Fuses

(L) Telecommunication Equipment including:

Telephones

Videophones

Fascimile machines/Fax cards

Tele-Printers/Telex machine

PABX/EPABX/ RAX/MAX Telephone Exchange

Multiplexers/Muxes

Modems

Telephone answering machines

Telecommunication Switching Apparatus

Anetna and Mast

Wireless datacom equipment

Receiving equipments like Pagers, mobile/Cellular Phones, etc.

VSATs

Video Conferencing Equipments

* Including Set Top Boxes for both Video and Digital Signaling.

(M) IT Enabled Services are business processes and services, the end products/services of which are:-

- Delivered outside India.
- Delivered over communication network., and
- Either externally contracted (out-sourced) or provided by a remote subsidiary of the same company (out-located).

Note: Services which would not be included are:-


- Remote production/manufacturing units
- The Corporate offices of companies or their local branches
- Virtual business on Internet.


The following services which meet the above criteria would be included:-

- (i) Back-Office Operations
- (ii) Call Centres
- (iii) Content Development or Animation
- (iv) Data Processing
- (v) Engineering and Design
- (vi) Geographic Information System Services
- (vii) Human Resource Services
- (viii) Insurance Claim Processing
- (ix) Legal Database
- (x) Medical Transcription

- (xi) Payroll
- (xii) Remote Maintenance
- (xiii) Revenue Accounting
- (xiv) Supports Centres and
- (xv) Web-site Services.

A. K. SINGH, Principal Secretary to Government Haryana, Town and Country Planning Department.





57197—C.S.—H.G.P., Chd.